

ALLEGAN COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Allegan Located in. Corner Code #  
(County)

1. Public Land Survey T 4N R 14W H-10  
 T \_\_\_ R \_\_\_ Center  
 T \_\_\_ R \_\_\_ Sec. 27  
 T \_\_\_ R \_\_\_ Overisel Twp.

2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
 in Section S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
 Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_

1995 DEC 14 PM 2:36  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICHIGAN  
 E I I E N

SURVEY &  
 REMONUMENTATION

APR 29 1996

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk L. Van Order, in a field survey on March 28, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-10  
 •GLO did not set  
 •MacDougall survey recorded May 11, 1905 indicates stone at corner.  
 2690.2' to N 1/4 corner Sec. 27  
 2639.1' to E 1/4 corner Sec. 27  
 2668.2' to S 1/4 corner Sec. 27  
 2620.4' to W 1/4 corner Sec. 27

(continued on back)


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-10  
 Kirk L. Van Order survey Mar. 28, 1995  
 Fd. stone with depression in top with iron along side by use of iron ties as stated in April 6, 1984 survey

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Peer group approved Oct. 10, 1995.

Distance traversed: off road = 5357.54' on road = 5260.20'



APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 10-10-95  
 COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-10  
 Removed stone and iron and set standard Allegan Co. Remon. monument (3/4" x 30" steel rod w/red cap #23520)

Nail & Remon. tag in S side 24" Spruce	AZ. 79°26'	155.82'
Nail & Remon. tag in W side power pole	AZ. 179°23'	36.62'
SW corner conc. foundation to metal bldg.	AZ. 330°10'	199.30'
SE corner conc. foundation to metal bldg.	AZ. 340°56'	181.17'
N 1/4 corner Sec. 27	N00°04'17"E	2689.54'
E 1/4 corner Sec. 27	S86°25'16"E	2639.66'
S 1/4 corner Sec. 27	S00°02'55"W	2668.00'
W 1/4 corner Sec. 27	N86°23'50"W	2620.54'

Signed by [Signature] Date 12-13-95  
 Surveyor's Michigan License No. 23520

0005 PAGE 277

H-10

•GLO did not set

•MacDougall survey recorded May 11, 1905 indicates stone at corner  
 2690.2' to N 1/4 corner Sec. 27  
 2639.1' to E 1/4 corner Sec. 27  
 2668.2' to S 1/4 corner Sec. 27  
 2620.4' to W 1/4 corner Sec. 27

(continued on back of sheet)

H-10

Kirk L. Van Order survey Mar. 28, 1995

Fd. stone with depression in top with iron along side by using same ties as stated in April 6, 1984 survey

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Peer group approved Oct. 10, 1995.

Distance traversed: off road = 5357.54' on road = 5260.20'

H-10

Removed stone and iron and set standard Allegan Co. Remon. monument (3/4" x 30" steel rod w/red cap #23520)

Nail & Remon. tag in S side 24" Spruce	AZ. 79°26'	155.82'
Nail & Remon. tag in W side power pole	AZ. 179°23'	36.62'
SW corner conc. foundation to metal bldg.	AZ. 330°10'	199.30'
SE corner conc. foundation to metal bldg.	AZ. 340°56'	181.17'
N 1/4 corner Sec. 27	N00°04'17"E	2689.54'
E 1/4 corner Sec. 27	S86°25'16"E	2639.66'
S 1/4 corner Sec. 27	S00°02'55"W	2668.00'
W 1/4 corner Sec. 27	N86°23'50"W	2620.54'