

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

1995 DEC 14 11:23:36
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 FILED

For corners in
Allegan (County) Located In: Corner Code #

1. Public Land Survey T4N R14W K-2
 T R W 1/4 Cor.
 T R Sec. 1
 T R E 1/4 Cor.
 T R Sec. 2
 T R Overisel Twp.

2. Property Controlling Sec. 1 T R
 S T R
 S T R

3. Miscellaneous Property in Sec. S T R
 S T R

Register of Deeds Stamp & File Number

SURVEY &
 REMONUMENTATION

APR 29 1996

COMMISSION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gerald T. Ford, in a field survey on March 23, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-2 General Land Office Survey Notes, 1931 Surveyor- Lucius Lyon Post 3" Sugar S 51° E 22 links 12" White Ash N 70° N 25 links	Allegan Co. Surveyor Notes August 26-29, 1875 Stone and crockery Distance K-2 to K-1 2789.5' Distance K-2 to K-3 2660.0' Distance K-2 to K-3 indicated as being "WRONG"
--	--

Nederveld & Assoc.
 Job #932030
 May 8, 1993
 Found 1" sq. iron in mon. box
 Nail S side p. pole S75°W 41.72'
 "X" mark in centerline top of 36"
 CMP .2' from end S40°E 53.42'
 Nail top of 4"x6" wood fence post
 N40°E 61.36'
 Nail E side p. pole N40°W 144.70'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-2 Found 1" square bolt in mon. box Nail S side power pole Nail centerline top of 4"x4" post Nail E side power pole "X" cut in centerline top of 36" CMP Mon. box (K-3) Old fence line near the S 1/8 line of Sec. 1 extended West Old fence line near S 1/8 line of Sec. 2 extended East 1/2" Re-bar (K-1) 1" Steel bar (K-2)	SW 41.62' SE 56.14' N 40° W 144.70' S 40° E 53.44' S 2634.8' S 1317.1' S 1317.1' N 2816.2' E 5263.2'
---	--

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY

DATE APPROVED 12-5-95
 COUNTY REP. *[Signature]*

Replaced 1" square bolt in monument box with A. C. Remon. iron and cap.

Approved by the Allegan Co. Remonumentation Peer Group on December 5, 1995, and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2 Allegan County Remonumentation iron and cap in monument box A. C. Remon. nail & tag SE face Power pole A. C. Remon. nail & tag E face Power pole "X" cut in E end centerline top of 36" CMP road culvert "X" cut in W end centerline top of 36" CMP road culvert Centerline E-W gravel road 12' North	AZ 250° 41.73' AZ 327° 144.56' AZ 144° 53.44' AZ 214° 50.26'
---	---

Signed by *Gerald T. Ford* Date November 14, 1995
 Surveyor's Michigan License No. 33976

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 ADAPTED FOR WORD PROCESSING MARCH, 1983