

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Allegan</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T4N R14W	M-2
Property Controlling in Section	T R	E 1/4 Cor.
3. Miscellaneous Property in Sec.	T R	Sec. 1
	T R	<u>Overisel Twp.</u>
	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1995 DEC 14 PM 2:36
REGISTER OF DEEDS
ALLEGAN COUNTY, MICHIGAN
REGISTER OF DEEDS STAMP & FILE NUMBER

FILED

**SURVEY &
REMONUMENTATION
APR 29 1996
COMMISSION**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gerald T. Ford, in a field survey on June 27, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-2 General Land Office Survey Notes, 1831 Lucius Lyon, Surveyor Post 7" Beech N 43° W 45 links 9" Beech S 13° W 22 links	Allegan Co. Surveyor Notes Aug. 26-29, 1875 Stake and stone Ratekin & Assoc. 1967 Iron over stone Power pole SW 44.5' Street sign ENE 20.2' 30" Cherry ESE 81.15' Telephone pole SE 27.65'	Nedervald Assoc. File No. 932030 May 5, 1993 1/2" iron pipe Nail NW side power pole S 45° W 45.02' Nail SW side guy pole S 45° E 28.12' Nail W side 6" Cherry N 35° E 38.94' Nail E side Power pole S 30° E 90.23'
---	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


M-2
Found 1" tapered steel bar over stone and wood stake under stone.
Nail NW side power pole AZ 218° 44.96'
Nail SW side guy pole AZ 133° 28.12'
Nail W side 6" Cherry AZ 35° 38.98'
Power pole AZ 162° 90.2'±

Replaced 1" steel bar and stone and set A.C. remon. iron and cap in center of remnants of wood stake. Approved by the Allegan County Remonumentation Peer Group on November 14, 1995 and is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 11-14-95
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2
A.C. Remonumentation iron and cap
A.C. Remon. tag and nail W face 6" Ash AZ 15° 78.43'
A.C. Remon. tag and nail W face power pole AZ 133° 28.01'
A.C. Remon. tag and nail W face power pole AZ 162° 90.27'
A.C. Remon. tag and nail NW face power pole AZ 218° 45.23'
At centerline of gravel road N-S & E



Signed by [Signature: Gerald T. Ford] Date November 13, 1995
Surveyor's Michigan License No. 33976

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 25, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983