

**SURVEY
REMONUMENTATION**

APR 29 1998

SECTION

**Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Allegan <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>4</u> N R <u>14</u> W	M-3 (SE, 1) Overisel Twp.
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBR0007/PAGE 50

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John C. Bueche, in a field survey on May 8, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-3 GLO, 1831	LCRC 2-87, Jan., 1973
Lucius Lyon, DS	Clapp
Set post Secs.	Set spk. 18' N of C/L
1 & 12	TP SW 54.40'
Beech 7 N 64 W 28	PP NW 117.75'
Sugar 4 S 12 W 31	St. sign NE 24.80'
	Salem Cor. South 30.07'

HEI inform.
No date
Stone 18' N of C/L
20" Maple SE 170.60'
26" Maple SW 98.70'
12" Hickory NW 241.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3 Found large spk. in Mon. Box	Set spk. 18' N of C/L	18' N of C/L
	TP SW 54.40' cut off	
	PP NW 117.75'	Peer group approved 6-9-98.
	Salem Cor. South 30.07'	

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED JUNE 9, 1998
COUNTY REP. [Signature]

And is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 Replaced spk. with 3/4" x 24" Pin with Allegan Co. Cap in Mon. Box
Nail & Allegan Co. Remon. Tag in NE side PP S 25° E 88.48'
Nail & Allegan Co. Remon. Tag in top of cut off pole S 35° W 55.13'
Nail & Allegan Co. Remon. Tag in S side 18" Walnut N 80° W 123.84'
Nail & Allegan Co. Remon. Tag in E side PP N 20° W 118.25'
C/L of conc. ROW marker N 60° W 49.24'
On C/L of gravel road N-S
C/L E-W bit. South 18'±; on C/L bit. West extended East
Allegan Co. Mon. in Mon. Box A-3 (NW 7, 4-13) South 30.24'



Signed by John C. Bueche Date 6-4-98

Surveyor's Michigan License No. 13027

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED JUNE 9, 1998
COUNTY REP. [Signature]