

**SURVEY  
REMONUMENTATION**

APR 29 1999

Allegan County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

Allegan (County)	Located in:	Corner Code #
1. Public Land Survey	T4N R14W	M-7 (SE, 13) Overisel Twp.
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

FILED  
1/28/1999 2:44:39 PM  
JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

LIBERO 007 PAGE 53

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John C. Bueche, in a field survey on May 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
M-7 GLO, 1831  
Lucius Lyon, DS  
Set post for Secs. 13 & 24  
Elm 14 S 41 W 87  
W. Ash 7 N 66 E 30

LCRC 3-228, Jan., 1979  
Clapp  
Fnd. steel bar  
St. sign SE 7.68'  
C/L pave. N 14'  
Salem Twp. cor. N. 33.37'

LCRC 3-359, April, 1983  
Bonnema  
Fnd. steel bar  
St. sign SE 7.78'  
C/L pave. N 14.3'  
Mon. Box Salem cor. N. 33.40'  
PK in NE side TP SE 51.80'  
**OVER**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7 Found 1" x 18" steel bar in dirt shoulder

C/L pave. N 14'  
Salem Twp. cor. N. 33.37'

C/L pave. N 14.3'  
Mon. Box Salem cor. N. 33.40'  
Peer group approved 6-9-98.

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED JUNE 9 1998  
COUNTY REP. [Signature]

And is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 Replaced 1" steel bar with 3/4" x 36" Pin with Allegan Co. Cap  
Nail & Allegan Co. Remon. Tag in E side 22" Elm S 30° W 88.23'  
Nail & Allegan Co. Remon. Tag in S side PP N 75° W 157.47'  
Nail & Allegan Co. Remon. Tag in N side PP S 85° E 170.42'  
NW cor. metal bldg. S 45° W 113.25'  
SE cor. metal bldg. N 25° W 212.91'  
Allegan Co. Mon. A-7 (SW 18, 4-13) North 33.40'  
C/L bit. E-W, North 14±; C/L gravel road N. is East 6±



Signed by John C. Bueche  
Surveyor's Michigan License No. 13027

Date 6-4-98

SURVEY  
REMONUMENTATION

APR 29 1999

M-7 SECTION *VERISEL TWP.*  
PART A - continued

Survey Jan., 1982, Exxel  
St. sign SE 7.68'  
NE cor. metal bldg. SW 98.69'  
PK NE side TP SE 51.80'  
C/L bit. N. 14'  
Mon. Box Salem cor. N. 33.37'

HEI information  
Same as above

Survey Feb., 1992, Van Order  
Fnd. 1" steel rod  
PK in TP SSW 35.92'  
PK in TP SE 51.75'  
NE cor. metal bldg. SW 98.67'  
PK in wood post NW 64.77'  
S. edge bit. rd. N. 2.1'

LIBRO 007 PAGE 54