

MAR 07 2000

SECTION

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>14W</u>	<u>M-10</u> <u>Overisel</u> Twp.
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTER OF DEEDS
 ALLEGAN COUNTY
 [Signature]

00 FEB - 1 AM 8:49

FILED
 LENO 007 14th 16

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk L Van Order in a field survey on Nov 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-10
 (1) GLO
 North E. side Sec. 25
 40.00 Set 1/4 sec. post
 Beech 10" N.88°W. 20 links
 Do 12" N.07°W. 31 links

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED NOV. 9, 1999
 COUNTY REP. [Signature]

(continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10
 Fd. 1-1/2" x 36" iron pipe and the following witnesses:
 Nail in S. side 11" elm (now dead) W.SW 88.93'
 Nail in N. side 6" (now 7") ash SW 92.43'
 Power pole has been replaced
 Removed fd. iron pipe and replaced with standard Allegan Co. monument and is accepted as a careful and faithful perpetuation of the position of the original corner.
 Peer group approved Nov. 9, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10
 Standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)
 Nail & Remon. tag in E side power pole AZ 355° 78.89'
 Nail & Remon. tag in N side 7" ash AZ 235° 92.45'
 Nail & Remon. tag in N side 14" maple AZ 90° 82.17'
 Nail & Remon. tag in SW side 10" ash AZ 140° 70.27'

Signed by [Signature]
 Surveyor's Michigan License No. 23520

Date 12-30-1999

MAR 07 2000

SECTION

LIBRO 00 / PAGE 17

Section A (continued from Page 1)

M-10

Overisel Twp., T.4N., R.14W

- (2) LCRC recorded in Liber 1 on Page 391 by Donald A. Ratekin, dated June 6, 1972
 Witness card Fd. stone - set 1-1/2" iron pipe
 - 10" ash SSW 72.4'
 - 4" sycamore SW 59.75'
 - St sign N 37.0'
 - P pole NNW 82.0'
 - 1-1/2" iron pipe w/stake inside
 - 12" ash S45°W 72.4'
 - 6" sycamore S60°W 59.75'
 - St. sign N10°W 31.75' (was moved)
 - P. pole N05°W 82.0'
- (3) Holland Engineering, Inc. info.
 Same info as in No. 2 above
- (4) Kirk L. Van Order, R.L.S. survey recorded in Liber 1191 on Page 550, dated April 10, 1986
 Fd. 1-1/2" pipe
 - 16" ash SW 72.4'
 - 9" sycamore SW 59.75'
 - St. sign NW 31.75'
 - Power pole NW 82.0'
- (5) Kirk L. Van Order survey, dated May 17, 1989
 Fd. 1-1/2" pipe
 Same ties as in No. 4 above
- (6) Kirk L. Van Order survey dated, April 17, 1990
 Fd. 1-1/2" pipe
 Same ties as in No. 4 above
- (7) Kirk L. Van Order survey, dated May 12, 1993
 Fd. 1-1/2" pipe
 - Nail in S. side 11" elm W.,SW 88.93'
 - Nail in N. side 6" ash SW 92.43'
 - Nail in NW side 12" elm S.,SW 100.96'
 - PK in E. side power pole N.,NW 82.49'