

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T4N R15W	A-11
	T R	SW cor. Sec. 30,
	T R	Fillmore Twp.
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1995 DEC 14 PM 2:33
ALLEGAN COUNTY REGISTER OF DEEDS

FILED

**SURVEY &
REMONUMENTATION**

APR 29 1986

COMMISSION

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Steven Lampen, in a field survey on March 23, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
A-11
GLO - 1831, Britain Survey in L 883-P 521, 1975
Intersect with boundary S 10 links NE corner Sec. 36, T4N, R16W
of post & set post. Found 3/4" iron
18" Maple S 60° E 16' "T" iron S 6.6'
6" Birch N 57 1/2° E 22'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-11
Found "T" iron in mon. box on E line Sec. 36, T4N, R16W, and accepted it as a careful and faithful perpetuation of the position of the original corner.
3/4" iron in mon. box N 5.65'
Approved by Allegan County Remonumentation Peer Group, December 5, 1995

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 12-5-95
COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-11, T4N, R16W
Found "T" iron in mon. box on E line Sec. 36, set Allegan Co. Remon. iron and cap in Mon. box
AZ = MI State plane grid direction

M-11, T4N, R16W	0° 12' 37"	6.65'
Power pole Remon. tag W side	30° 33'	145.58'
Power pole Remon. tag SW side	305° 15'	84.72'
Power pole Remon. tag SW side	144° 58'	52.28'
24" Poplar Remon. tag W side	30° 58'	240.59'
M-12, T4N, R16W	180° 12' 37"	



Signed by Steven Lampen Date December 5, 1995
Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1982
ADAPTED FOR WORD PROCESSING MARCH, 1982