

RF

MAR 6 7 2000

ALLEGAN COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in SECTION

00 FEB -1 AM 8:39

ALLEGAN
(County)

Located In: FILLMORE Corner Code #
(Township)

- 1. Public Land Survey T 4N R 15W A-12
T R
T R WEST 1/4 CORNER
T R SECTION 31
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous S T R
Property in Sec. S T R
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Joyce A. Elliott

REGISTER OF DEEDS
ALLEGAN COUNTY

Register of Deeds Stamp & File Number

1111111111 / 1111111111

I, Robert E. Lemke, surveyor, in a field survey on March 13, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G.L.O. DID NOT SET

1919 HUGH McDOUGAL, COUNTY SURVEYOR NOTES FROM MAY 23, 1919
FOUND 2 STONES AT THE WEST 1/4 POST. HE THINKS THE NORTH ONE IS FOR LAKETOWN TOWNSHIP.

1982 JOHN H. DILLINGHAM, BOUNDARY SURVEY DATED 10-25-82
SHOWS WEST 1/4 CORNER ON DRAWING, BUT NO WITNESSES SHOWN.
A-13 TO A-11 = 5277.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-12
FOUND 1/2" IRON BAR WITH CAP (HEI #14091)

MEASURED FROM A-12 TO A-13 = 2634.03'
MEASURED FROM A-12 TO A-11 = 2636.75' (SPLIT=2635.39' FOR FILLMORE TOWNSHIP BETWEEN A-13 AND A-11)
MEASURED FROM A-13 TO M-12 = 2638.66'
MEASURED FROM M-12 TO M-11 = 2638.79' (SPLIT=2638.72' FOR LAKETOWN TOWNSHIP BETWEEN A-13 AND M-11)
MEASURED FROM A-12 TO M-12 = 4.63'
MEASURED FROM A-11 TO M-11 = 6.66' (G.L.O = 6.6')

FOUND 1/2" IRON BAR AT A-12 IS 1.36' SOUTH OF SPLIT FROM A-13 TO A-11 AND IS ON LINE BETWEEN A-13 AND M-12.
HOLLAND ENGINEERING, INC. PLACED A-12 PER JOG SHOWN ON OLD SURVEY.

(DISTANCE TRAVERSED=5277')

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER. SET 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON AND CAP #23520 IN MONUMENT BOX.

PEER GROUP APPROVED DECEMBER 14, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12
SET 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON AND CAP #23520 IN MONUMENT BOX.

SET NAIL WITH ALLEGAN CO. REMON. TAG ON EAST SIDE OF 36" DIAMETER TREE 24" ABOVE GROUND.	N 08° W	320.41'
FOUND NAIL WITH ALLEGAN CO. REMON. TAG ON SOUTH SIDE OF WOOD POWER POLE 36" ABOVE GROUND.	N 89° W	130.40'
FOUND NAIL WITH ALLEGAN CO. REMON. TAG ON S.E. SIDE OF WOOD POWER POLE 36" ABOVE GROUND.	S 26° W	289.65'
CENTER OF SOUTH END OF A 12" DIAMETER METAL CULVERT ON EAST SIDE OF 60 TH STREET.	N 79° E	25.70'
CENTER OF NORTH END OF A 12" DIAMETER METAL CULVERT ON EAST SIDE OF 60 TH STREET.	N 41° E	38.33'
LAKETOWN TOWNSHIP CORNER	NORTH	4.63'
CENTERLINE OF 60 TH STREET	EAST	0.8'

Signed by Robert E. Lemke Date 12-30-1999

For SDI CONSULTANTS, LTD

Surveyor's Michigan License No. 40160

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED DEC. 14, 1999
COUNTY REP. [Signature]