

COPY

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan (County) Located in: Corner Code #

1. Public Land Survey T3N R15W * A-1 (NW, Sec. 6)
T R Manlius Twp.
T3N R16W M-1 (NE, Sec. 1)
T R Saugatuck Twp.

2. Property Controlling S T4N R15W M-13 (SE, Sec. 36)
in Section S T R Laketown Twp.

3. Miscellaneous S T4N R15W * A-13 (SW, Sec. 31)
Property in Sec. S T R Fillmore Twp.

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

97 JAN 22 PM 1:25
REGISTERED LAND SURVEYOR
ALLEGAN COUNTY
Register of Deeds Stamp & File Number

I, Steven Lampen, in a field survey on December 10, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-1
GLO - L. Lyon 1831 County Notes Kirk VanOrder, 1991 Survey
Beech 6 N 8 W 4 Found 1 3/4" pipe 1967 Capped iron in monument box
Sugar 10 S 10 W 5 Street sign SW 34.6' Telephone pole SE 48.44'
Stop sign NW 41.5' Power pole ESE 114.56'
Road Commission Power pole NE 78.0' NW barn corner SE 123.20'
P.K. in power pole NE 78.60' Telephone pole SE 48.3' Power pole SW 151.31'
P.K. in power pole ESE 114.70' NW corner garage SE 147.85' Power pole NE 78.48'
P.K. in power pole SW 151.31' County Records - 1924 Kirk VanOrder, 1980 Survey
Face of 7" Maple SE 92.00' 12" Elm SE 59.2' Set P.K., P.K. power pole NE 78.60,
P.K. in pavement N 100' & 200' SE corner headwall NE 31.8' P.K. power pole ESE 114.70', P.K. power pole
SW corner headwall NW 31.8' SW 151.31', face 7" Maple 92', centerline
monument box NE 0.65'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1
Found capped iron in monument box Power pole SW 151.31'
Face 7" Maple SE 92' Power pole NE 78.48'
P.K. power pole NE 78.60' Telephone pole SE 48.44'
P.K. power pole ESE 114.70' Power pole NW 135.30'
Telephone pole SE 48.44' Power pole SW 151.65'
Power pole ESE 114.56' Power pole NE 78.0'
NW Barn corner. SE 123.20' Telephone pole SE 48.3'

Replaced capped iron with 3/4"x24" Allegan County Remonumentation iron and cap and is accepted as a careful and faithful perpetuation of the original corner.


This corner approved by Allegan County Surveyors Peer Group on December 10, 1996

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 12-10-96
COUNTY REP. *Kirk VanOrder*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1
3/4"x24" Allegan County Remonumentation iron and cap in monument box in centerline asphalt road section.
AZ = Michigan State Plane grid direction

Power pole Remon. tag and nail W'ly side	18° 28'	78.49'
Power pole Remon. tag and nail S'ly side	304° 11'	135.21'
Power pole Remon. tag and nail E'ly side	227° 10'	151.32'
NW corner barn (concrete block)	144° 43'	123.05'
USC & GS Station Koutman	89° 12' 49"	2055.07'



Signed by *Steven Lampen* Date December 12, 1996
Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 16, 1971
REVISED MAY 14, 1975
REVISED JAN., 1982
ADAPTED FOR WORD PROCESSING MARCH, 1983