

COMMISSION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>15W</u>	<u>B-1 (N 1/4 Sec 6)</u>
	T _____ R _____	<u>Fillmore Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1993 DEC 30 PM 2:45
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
 Register of Deeds Stamp & File Number

FILED

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David R. Greer, in a field survey on November 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1 This corner not set by the Government

Recorded in Liber 2, Page 91, May 8, 1973	Recorded in Liber 1, Page 134 Oct 28, 1971	Recorded in Liber 4, Page 12, Mar. 13, 1987
Power Pole SW 33.75'	CL Fire Hydrant N35°W 45.8'	SW Cor Hse Fnd NE 87.36'
Power Pole NW 33.04'	CL MH in Gutter N50°E 36.0'	NW Cor Hse Fnd SE 116.57'
Guy Pole NE 40.22'	CL MH in Gutter S50°E 35.6'	NE Cor Hse Fnd SW 119.56'
	1/2" Pipe E 5.09'	NE Cor Hse Fnd NW 105.71'
		S 1/4 Cor Sec 31 E 5.09'


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1
 Found steel bar in monument box 0.59 South of the South line Sec 31, T5N R15W which fits the above witnesses. Set A.C. remonumentation iron and cap on South line of Section 31, T5N R15W 0.59 North of closing corner. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1
 A.C. Remon Iron & Cap on S line Sec 31, T5N R15W
 AZ - Michigan State Grid Direction

Found Steel Bar in mon. box	AZ. 179°30'01" 0.59
O.C. Remon iron B-13 S1/4 Sec 31 T5N R15W	AZ. 90°41' 5.07'
NE Corner House Foundation	AZ. 326°54' 104.65'
NW Corner House Foundation	AZ. 37°59' 106.24'
NW Corner House Foundation	AZ. 127°07' 116.96'
NE Corner House Foundation	AZ. 235°00' 119.88'



Signed by David R. Greer Date Nov. 19, 1993
 Surveyor's Michigan License No. 16042

W:\Decl\Sur\James.Jac

LIBER 004 PAGE 348

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1973
 REVISED JAN., 1983