

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74; Mich. P.A. 1970

1995 DEC 14 PM 2:33
 FILED
 Register of Deeds Stamp & File Number

For corners in
Allegan
 (County)

Located in: T4N R15W

Corner Code # C-11

1. Public Land Survey
 T ___ R ___
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling
 in Section S ___ T ___ R ___
 S ___ T ___ R ___
 S ___ T ___ R ___
 S ___ T ___ R ___

3. Miscellaneous
 Property in Sec. S ___ T ___ R ___

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

**SURVEY &
 REMONUMENTATION
 COMMISSION**

APR 29 1996

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gerold T. Ford, in a field survey on October 11, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 C-11
 Government Land Office
 Survey Notes, 1831
 Surveyor, Lucius Lyon
 Post
 12" Sugar N 85° W 20 links
 18" Beech S 81° E 36 links

Nederveld Associates
 File No. 912104
 May 15, 1991
 1/2" iron in monument box
 Power pole S 50° W 103.91'
 Telephone pole-cut off N 45° E 41.77'
 Service pole N 10° E 157.00'
 Power pole N 25° W 195.87'

Kirk L. VanOrder
 Job No. 91-2422
 Found 1/2" pipe in monument box
 Wood post NX 41.80'
 Street sign SE 51.27'
 Gas line post 88E 72.10'
 Power pole SW 103.93'


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 C-11
 Found 1/2" iron pipe in monument box
 Found nail & tag SE face power pole AZ 230° 103.91'
 Found nail & tag NW face cut off power pole AZ 44° 41.99'
 Found spike in E face of power pole AZ 11° 157.01'
 Found P.K. in W face of power pole AZ 335° 195.90'

Replaced iron pipe with A. C. Remon. iron and cap.

Approved by the Allegan Co. Remon. Peer Group on December 5, 1995 and is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 12-5-95
 COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 C-11
 Allegan County Remonumentation iron and cap in monument box
 A. C. Remon. tag & nail in SE face of power pole AZ 230° 103.90'
 A. C. Remon. tag & nail in E face of power pole AZ 11° 156.99'
 A. C. Remon. tag & nail in W face of 12" Ash AZ 60° 114.32'
 A. C. Remon. tag & nail in W face of power pole AZ 335° 195.60'
 SE Corner of cinder block garage (1' above ground) AZ 41° 215.91'



Signed by *Steven Lampen* Date November 14, 1995
 Surveyor's Michigan License No. 33976

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 29, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983
 ADAPTED FOR WORD PROCESSING MARCH, 1985