

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE.

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ALLEGAN COMMISSION

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T4N R15W C-13  
T R SE cor., Sec. 31  
T R Fillmore Twp.  
T R  
T R  
T R

2. Property Controlling S T R  
in Section S T R  
S T R

3. Miscellaneous S T R  
Property in Sec. S T R

97 JAN 22 PM 1:22  
REGISTER OF DEEDS  
ALLEGAN COUNTY  
FILED  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	-6	-5	4	-3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	-31	-32	-33	-34	-35	36							
13													

I, Steven Lampen, in a field survey on December 10, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- C-13 Road Commission  
GLO - L. Lyon - 1831 Iron in field south 57.08'  
Set post PK's in pavement North on  
Bench 22 N 71 W 11' line 75', 100' and 200'  
Sugar 8 N 74 W 44'
  - John Clapp - 1977  
Set 1/2" iron over stone and bricks  
Telephone pole ESE 74.0'  
Power pole WNW 64.25'  
Street sign WNW 95.20'  
Power pole ENE 98.44'
  - GLO - C-1, T3N, R15W  
Is 2.62 chains W of C-13  
Telephone pole ESE 74.0'  
Power pole WNW 64.25'
  - Hicks - 1876  
Stone at corner  
C-13 to C-12 = 2638.02' C-13 to C-12 = 2640.02'  
C-13 to D-13 = 2637.36' C-13 to D-13 = 2637.62'

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- C-13  
Found 1" iron in monument box  
C-13 to C-12 Clapp = 2640.02' measure = 2640.07'  
C-13 to D-13 Clapp = 2637.62' measure = 2637.93'  
Iron in monument box West 172.96'


Replaced 1" iron with 3/4"x24" Allegan County Remonumentation iron and cap and accepted it as a careful and faithful perpetuation of the original corner.

Approved by Allegan County Surveyors Peer Group on December 10, 1996.

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 12-10-96  
COUNTY REP. *Red & Alan Clapp*

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- C-13  
3/4"x24" Allegan County Remonumentation iron and cap in monument box.  
Azimuth = Michigan State Plan grid direction.

Remon. tag in East side power pole	344° 39'	80.30'
Remon. tag in Southeast side power pole	71° 00'	102.35'
Remon. tag in Southwest side power pole	130° 09'	116.04'
Remon. tag in Northwest side power pole	228° 11'	51.59'
C-1, T3N, R15W	270° 26' 11"	172.96'



Signed by Steven Lampen Date DECEMBER 12, 1996  
Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 29, 1931  
REVISED MAY 14, 1975  
REVISED JAN. 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1989