

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

1993 DEC 30 PM 2:45
REGISTER OF DEEDS
ALLEGAN COUNTY, MICHIGAN

FILED

For corners in
Allegan (County)

1. Public Land Survey	Located In:	Corner Code #
2. Property Controlling in Section	T <u>4N</u> R <u>15W</u>	<u>D-1 (N-1/4 Sec-5)</u>
3. Miscellaneous Property in Sec.	T _____ R _____	<u>Fillmore Twp.</u>
4. Lot No. _____, Recorded Plat _____	T _____ R _____	_____
5. Private Claims _____	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24	25	26	27	28		
9												
10	30	29	28	27	26	25	24	23	22	21	20	19
11												
12	31	32	33	34	35	36	37	38	39	40	39	38
13												

I, David R. Greer, in a field survey on November 19, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1 This corner not set by the Government
Recorded in Liber 2 Page 45, Nov 21, 1972

Power Pole	N	74.44'
Power Pole	SSE	30.72'
Guy Pole	SW	43.38'
Street Sign Post	ENE	54.63'

Recorded in Liber 2, Page 100, July 16, 1973

1/2" Iron	S	30.72'
PK in Side Power Pole	SW	43.40'
PK in Side Guy Pole	NE	59.46'
CL Hydrant	E	19.40'
Iron for Sec 33		


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1
Found steel bar 0.47 South of the South line of Section 32, T5N, R15W, which fits the above witnesses. Set A.C. Remonumentation Iron & Cap on the South line, Sec. 32, T5N, R15W, 0.47 North of the above corner. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1
A.C. Remon iron & cap on S line Sec 32, T5N, R15W
AZ - Michigan State Grid Direction
Fnd steel bar (closing corner)
O.C. Remon iron & cap D-13 S1/4 Sec 32 T5N R15W
NW House Corner, Brick
SE House Corner, Brick
SW Garage Corner, Foundation
SE House Corner, Foundation
SE House Corner, Foundation
SW Church Corner, Foundation

AZ. 179°54'28"	0.47'
90°40'	19.41'
AZ. 235°47'	114.94'
AZ. 211°36'	114.68'
AZ. 155°12'	162.79'
AZ. 324°18'	58.01'
AZ. 340°12'	109.52'
AZ. 53°25'	166.21'



Signed by David R. Greer
Surveyor's Michigan License No. 16042

Date 11/19/93

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JUN. 25, 1971
REVISED MAY 14, 1975
REVISED JAN., 1982

LIBER 001 PAGE 349