

# SURVEY & REMONUMENTATION

APR 07 1998

## Allegan County Remonumentation LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Register of Deeds  
 ALLEGAN COUNTY, MICH.  
*Joyce A. Carter*

98 JAN 21 PM 1:21

FILED

For corners in **SECTION**  
Allegan  
(County)

Located in: Corner Code #

- |                                    |                         |   |
|------------------------------------|-------------------------|---|
| 1. Public Land Survey              | T 4N R 15W              | <input checked="" type="checkbox"/> D-13 South 1/4 corner, Section 32 Fillmore Twp. |
|                                    | T _____ R _____         |   |
|                                    | T _____ R _____         |   |
|                                    | T _____ R _____         |   |
|                                    | T _____ R _____         |   |
| 2. Property Controlling in Section | S _____ T _____ R _____ |   |
|                                    | S _____ T _____ R _____ |   |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ |   |
|                                    | S _____ T _____ R _____ |   |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Steven Lampen, in a field survey on December 29, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

D-13  
 G.L.O.  
 Beech 7" N 83 1/2 W 33  
 Do. 16 N 74 E 62

D-13 to C-13, Hicks 1876 = 2637.36'  
 meas. 1997 2637.93'  
 D-13 to E-13, Hicks 1876 = 2637.36'  
 meas. 1997 2636.73'

J. W. Hicks, 5/11/1876  
 Stake and stone

South 1/4 post - fd stone placed 1" iron on top (10/13/67)  
 4" white post N 23.44'  
 8" Maple NW 57.6'  
 SE cor. house NW 106.0'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

D-13  
 Found iron in monument box  
 8" Maple NW 57.6'  
 SE cor. house NW 106.0'

Replaced iron with 3/4"x24" Allegan County Remonumentation iron and Remonumentation cap and accepted it as a careful and faithful perpetuation of the position of the original corner.


This corner was approved by the Allegan County Surveyors Peer Group on December 30, 1997.

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 12-30-97  
 COUNTY REP. K.V.O.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

D-13  
 Allegan County Remonumentation iron and cap in monument box  
 Remonumentation tag S. face power pole 75° 21' 132.34  
 SE corner garage foundation 337° 57' 102.46  
 SE corner house brick 317° 17' 105.81  
 D-1, T3N, R15W 270° 25' 162.30  
 Remonumentation tag N side power pole 290° 41' 103.98  
 Nail in E side 20" Maple 332° 28' 58.06  
 Nail in SW side 24" Maple 309° 59' 78.02  
 Centerline East and West asphalt road 180° 0.50

Azimuth = Michigan State Plane grid direction



Signed by Steven Lampen

Date DECEMBER 31, 1997

Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1976  
 REVISED JAN., 1983  
 ADAPTED FOR WORD PROCESSING MARCH, 1992