

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

CO-CURNION
 For corners in

1993 DEC 30 PM 2:41
 DEPARTMENT OF LAND & WATER
 ALLEGAN COUNTY, MICHIGAN
David R. Greer

FILED

<u>Allegan</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>4N</u> R <u>15W</u>	<u>E-1 (NW Sec 4)</u>
	T _____ R _____	<u>Fillmore Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	15	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David R. Greer, in a field survey on November-19, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


E-1 Government Notes 1831 Post			
Hemlock 14"	S20°E	9 links	
Maple 20"	S21°W	29 links	
Recorded in Liber 2, Page 44, Nov. 21, 1972		Recorded in Liber 2, Page 100, July 16, 1973	
Nail in Power Pole	SE	43.32'	RR Spike
MSHD Nail in Light Pole	NW	52.40'	PK in Side Power Pole
Nail in Guy Pole	NNE	102.81'	PK in Side Guy Pole
Nail in Tele. Pole	WSW	88.30'	NWly Cor Gas Station
			Iron for Sec. 33, Holland
			E
			21.20'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1
 Found railroad spike over concrete monument on South line of Section 32, Town 5 North, Range 15 West. Replaced with A.C. Remonumentation Iron & Cap and accepted it as a careful and faithful perpetuation of the position of the original corner
 RR Spike
 PK in Side Power Pole SE 43.35'
 PK in Side Guy Pole SW 52.30'
 NWly Cor Gas Station ESE 89.85'
 Iron for Sec. 33, Holland E 21.20'
 Nail in Guy Pole NNE 102.81'
 Nail in Tele. Pole WSW 88.30'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1	A. C. Remon Iron & Cap on SW Cor, Sec 33, T5N R16		
	AZ - Michigan State Grid Direction		
	D.C. Remon Iron E-13 SW Cor, Sec 33, T5N, R15W	AZ. 90°43'21"	21.25'
	NW Corner Brick Building	AZ. 146°42'	121.89'
	SW Corner Brick Building	AZ. 150°27'135.59"	CL Hydrant AZ. 358°41' 122.69'
	SW Corner Brick Building	AZ. 54°27'112.05"	NW Cor Bldg. AZ. 35°43' 164.50'
	SE Corner Brick Building	AZ. 56°01'	NE Cor Bldg. AZ. 252°05' 156.22'
			116.38'



Signed by David R. Greer Date 11/19/93
 Surveyor's Michigan License No. 16042