

**SURVEY &
REMONUMENTATION**

APR 07 1998

**Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **SECTION**
Allegan
(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|-----|------|------------------|
| 1. Public Land Survey | T4N | R15W | ✓ E-13 SE corner |
| | T | R | Section 32 |
| | T | R | Fillmore Twp. |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

98 JAN 21 PM 1:22
FILED
James A. Bittu
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.
Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, Steven Lampen, in a field survey on December 29, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|--------------------------|---|-----------------------|
| E-13 | LCRC L 2, P 217 | LCRC L 2, P 273 |
| GLO L. Lyon 1831 | D.A. Ratekin & Assoc., Inc. 3/19/73 | Kistler & Assoc. |
| 12" Beech N 65 E 17 | NE cor. porch SE 76.65' | Fd. steel bar |
| 18" Beech N 32 W 28 1/2 | NW cor. porch S 58.6' | 20" Ash SSW 87.40' |
| | T.P. NW 43.2' | Tel. pole SW 38.41' |
| | Catalpa SW 43.45' | T. pole NW 42.93' |
| | | 10" Hemlock NW 49.16' |
| J. W. Hicks, May 1876 | H.E.I. Reset Steel Bar 1982 | |
| Stake and stone | Kirk L. VanOrder 6/7/83 | |
| D-13 to E-13 = 39.96 ch. | Fd. steel bar | |
| | (fd. iron in mon. box WNW 1.09' from true cor.) | |
| A. Gardner 1879 | 20" Ash WSW 110.65' | |
| Stone | 24" Ash SSW 87.40' | |
| E-13 to F-13 40.00 chns | SW corner block building NE 114.75' | |
| | SE corner house foundation NW 130.34' | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | |
|---|------------------------------|
| E-13 | E-13 to D-13 measure 2636.74 |
| Fd. 1/2" steel bar | E-13 to F-13 measure 2639.98 |
| 20" Ash SSW 87.40' | |
| 20" Ash WSW 110.65' | |
| SW corner concrete building. NE 114.75' | |
| SE corner house foundation. NW 130.34' | |


Replaced iron with 3/4"x24" Allegan County Remonumentation iron and Remonumentation cap and accepted it as a careful and faithful perpetuation of the position of the original corner.

This corner was approved by the Allegan County Surveyors Peer Group on December 30, 1997.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 12-30-97
COUNTY REP. K.V.O.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|--|--|---|
| E-13 | Allegan County Remonumentation iron and cap. | Azimuth = Michigan State Plane grid direction |
| Re-monumentation tag in W face 24" Ash | AZ 194° 17' | 88.47' |
| Re-monumentation tag in NW face 24" Ash | AZ 247° 55' | 109.84' |
| SE corner house foundation | AZ 301° 04' | 130.35' |
| SW corner block building | AZ 24° 12' | 114.75' |
| NE corner foundation. building | AZ 115° 57' | 155.10' |
| E-1, T3N, R15W | AZ 270° 26' | 151.83' |
| NW corner house foundation | AZ 120° 50' | 129.61' |
| Centerline East and West asphalt road pavement | AZ 0° | 0.0' |



Signed by Steven Lampen Date DECEMBER 31, 1997

Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983