

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
**Allegan**  
(County)

Located in:

Corner Code #

1. Public Land Survey	T	<u>4N.</u>	R	<u>15W.</u>	<u>F-1 (N 1/4 Sec 4)</u>
	T	_____	R	_____	<u>Fillmore Twp.</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

1993 DEC 30 PM 2:45  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.  
*Joyce A. Blatter*

**FILED**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David R. Greer, in a field survey on November 19, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1 This corner not set by Government  
Recorded in Liber 3, Page 89, Oct. 22, 1976  
1/2" Iron  
Power Pole NE 33.02'  
Power Pole WNW 121.22'  
Iron for Section to NE 71.90'  
PK Top Fence Post S 30.97'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1  
Found concrete monument in monument box on the South line of Section 33, T5N, R15W. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.  
Power Pole NE 33.02'  
Power Pole WNW 121.22'  
Iron for Section to NE 71.90'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 T4N, R15W  
Replaced concrete monument in monument box with A.C. Remonumentation Iron & Cap on the S. Line Sec 33, T5N, R15W  
AZ = Michigan State Grid Direction  
O.C. Remon iron & cap F-13 S1/4 Sec3 T5NR15W AZ. 90°48' 71.94'  
NE Cor Bldg. AZ. 193°47' 100.60'  
NW Cor Bldg, Siding AZ. 217°47' 122.79'  
O.C. Remon tag & nail in S Side Power Pole AZ. 285°38' 121.95'  
A.C. Remon tag & nail in W Side Power Pole AZ. 34°03' 37.95'  
Fnd PK & tag #16042 in SW Side Light Pole AZ. 106°38' 202.28'



Signed by David R. Greer  
Surveyor's Michigan License No. 16042

Date 11/19/93