

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Allegan (County)

1. Public Land Survey	T <u>4N</u> R <u>15W</u>	<u>G-1 (NW-Sec-3)</u>
	T _____ R _____	<u>Fillmore Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1993 DEC 30 PM 2:41  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.  
*James E. Webster*  
**FILED**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, David R. Greer, in a field survey on November-10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate. Government Notes 1831 Post  
Lynn 20" S67°E 25 links  
Beech 5" S75°W 16 links

A. Description of original monument and accessories and/or subsequent restoration:  
G-1

Recorded in Liber 4, Page 64, March 16, 1990  
Found 1" Iron in Monument Box  
PK NW Side Power Pole NNE 30.85'  
PK NW Side Power Pole WSW 54.00'  
PK SE Side Power Pole SSW 51.80'  
PK NE Side Power Pole SE 68.90'


Recorded in Liber 4, Page 114, April 12, 1993  
Reset 1/2 rod with mon. box removed by road construction  
PK NW Side Power Pole SW 51.56'  
PK SE Side Power Pole NE 47.24'  
PK SW Side Power Pole SE 68.00'  
E 118.75' to the SW corner of Section 34, T5N, R16W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1  
Found concrete monument in monument box on South line of Section 35, Town 5 North, Range 15 West. Replaced with A. C. remonumentation iron and cap and accepted it as a careful and faithful perpetuation of the position of the original corner.  
PK NW Side Power Pole SW 51.56'  
PK SE Side Power Pole SE 47.24'  
PK SW Side Power Pole SE 68.00'  
E. 118.75' to the SW Cor of Section 34, T5N, R16W

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
G-1

A.C. Remon Iron & Cap  
AZ = Michigan State Grid Direction  
O.C. Remon Iron G13, SE Cor Sec33, T5N R15W  
Fnd PK SE Side Power Pole AZ. 90°42'34" 118.73'  
Fnd PK W Side Power Pole AZ. 22°32' 47.12'  
Fnd PK W Side Power Pole AZ. 211°19' 51.69'  
Fnd PK W Side Power Pole AZ. 142°22' 68.64'  
SW Cor Brick Bldg AZ. 72°27' 265.03'  
A.C. Remon tag & nail in W Side Power Pole AZ. 25°04' 189.74'  
SE Cor Building, Concrete AZ. 324°46' 127.21'



Signed by David R. Greer Date 11/19/93  
Surveyor's Michigan License No. 16042

W:\Deeds\Surv\Remon.doc

LIBER 004 page 275