

APR 07 1998

Allegan County Remonumentation LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Allegan (County) Located In: Corner Code # 1. Public Land Survey T4N R15W G-13 SE corner Section 33 Fillmore Twp. 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R 4. Lot No. Recorded Plat 5. Private Claims

98 JAN 21 PM 1:22 REGISTER OF DEEDS ALLEGAN COUNTY MICHIGAN FILED

Register of Deeds Stamp & File Number

I, Steven Lampen, in a field survey on December 29, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-13 GLO Lyon 1831 Lyon Set post corner, Sections 33 and 34 7" Beech N 41° E 13 10" Beech N 80° W 14 Consumers Power Company Set iron Street sign WNW 61.00 Power pole SE 28.33 Telephone pole WSW 83.42 Power pole NNE 55.92 Gardner 1879 Stone G-13 to F-13 39.70 ch Old County Records NE cor. Sec. 4, T3N, R15W W 126.72' Holland Engineering, Inc., Survey 1978, L 946, P 739 Power pole SE 39.10' Power pole NNE 55.84' Street sign SW 45.76' Telephone pole WSW 81.75 Road Commission Iron in roadway 100.00' N Iron in roadway 200.00' N

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-13 Found 3/4" pipe in monument box Found iron in roadway 54th Street 100.0' N Found iron in roadway 54th Street 200.0' N Power pole NNE 55.92' Power pole SE 39.10' Power pole NNE 55.84' Street sign SW 45.76

APPROVED REMONUMENTATION CORNER P.A. 345 OF 1990 ALLEGAN COUNTY DATE APPROVED 12-30-97 COUNTY REP. K.V.O.

Replaced pipe with 3/4"x24" Allegan County Remonumentation iron and Remonumentation cap and accepted it as a careful and faithful re-establishment of the original corner.

This corner was approved by the Allegan County Surveyors Peer Group on December 30, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-13 Allegan County Remonumentation with cap in monument box Azimuth = Michigan State Plane grid direction Power pole Remonumentation tag E side 151° 25' 39.19 Power pole Remonumentation tag W side 20° 34' 56.34 Power pole Remonumentation tag E side 328° 42' 56.34 G-1, T3N, R15W, Remonumentation tag in S side Power pole 270° 48' 126.74 Remonumentation tag in N side Power pole 286° 21' 170.93 Remonumentation tag in N side Power pole 104° 44' 141.29 Centerline East and West asphalt pavement 0° .0'

Signed by Steven Lampen Date DECEMBER 31, 1997 Surveyor's Michigan License No. 37279

