

APR 07 1998

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Allegan Located in: _____ Corner Code _____
_____ (County) _____

1. Public Land Survey T4N R15W H-13 (South 1/4
corner Section 34
Fillmore Township
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

98 JAN 21 PM 1:22
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.
FILED
Register of Deeds Stamp & File Number

I, Steven Lampen, in a field survey on December 29, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13
G.L.O. L. Lyon 1831
W. wood 32" N 41 W 9
Beech 10" W 63 E 52

C.P. Co. -
S 1/4 post 3/4" Iron "set"
4" Maple S 17.9'
24" Maple NW 79.47'
St. sign WNW 91.97'
P.P. NE 74.43'

H-13 to I-13
Old County Surveyors Records = 2624.1'
Consumers Power Company = 2624.48'
Measure = 2624.66'

S 1/4 post - Road Commission
P.K. in 18" Maple NW 79.08'
P.K. in P.P. NE 75.02'
P.K. in 18" Pear SSW 59.51'
N 1/4 post, T3N, R15W, Sec. 3 W 105.80'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13
Found 3/4" Iron in monument box
24" Maple NW 79.47'
P.P. NE 74.43'

Replaced iron with 3/4"x24" Allegan County Remonumentation iron and remonumentation cap and accepted it as a careful and faithful perpetuation of the original corner.


This corner was approved by the Allegan County Surveyors Peer Group on December 30, 1997.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 12-30-97
COUNTY REP. K.V.O.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13
Allegan County Remonumentation iron and Remonumentation cap in monument box.
Azimuth = Michigan State Plane grid direction

Remonumentation tag NW face Power Pole	44° 46'	74.97'
Remonumentation tag E face 10" W. Ash	160° 24'	48.15'
Remonumentation tag W face 10" Maple	205° 00'	46.04'
Remonumentation nail and tag N side 30" Maple	296° 56'	79.68'
SE corner brick house #5309	314° 21'	136.35'
H-1 T3N, R15W	270° 59'	105.38'
Centerline East and West asphalt pavement	180°	0.3'



Signed by Steven Lampen Date DECEMBER 31, 1997

Surveyor's Michigan License No. 37279