

SURVEY & REMONUMENTATION

APR 07 1998

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS  
ALLEGAN COUNTY MICHIGAN  
*James A. [Signature]*

98 JAN 21 PM 1:22

FILED

SECTION  
For corners in  
Allegan (County)

Located In: Corner Code #

- Public Land Survey T4N R15W ✓ I-1  
T R  
T R  
T R  
NW corner Section 2  
Fillmore Twp.
- Property Controlling S T R  
in Section S T R
- Miscellaneous S T R  
Property in Sec. S T R
- Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_
- Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, Steve Lampen, in a field survey on December 6, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- |                                                                                                                                                                                      |                                                                                                                                               |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------|
| I-1<br>G.L.O. - 1832 - Britain<br>77.45 to North boundary 170 links<br>West of post and set post corner<br>Section 2 and 3<br>Beech 3 South 58 W 24<br>Cherry 8 South 27 1/2 East 78 | I-1 - MSHD-1965<br>Found stone<br>I-1 - I-2 = 2497.90<br>I-1 - J-1 = 2669.48                                                                  |
| I-1 MacDougal<br>Stone<br>Catalpa 8° Northwest 29.70<br>Catalpa 8° North 28.30<br>Catalpa 8° Northeast 33.30                                                                         | I-1 Van Order - 1986<br>Found iron in monument box<br>Power pole Northeast 83.48<br>Power pole Southwest 50.58<br>21" Catalpa Northwest 29.96 |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1  
Found capped iron on South line of Section 34, Town 5 North, Range 15 West, set by Jerry Ford - Holland Engineering, Inc. in 1987 at the amended corner. Found iron in monument box at the closing corner, which is 2.05 feet South of the amended corner.

The following found witnesses and measurements are to the closing corner:  
20" Catalpa Northwest 29.70 Power pole Northeast 83.48 I-1 - I-2 measure 2498.20  
20" Catalpa North 28.30 Power pole Southwest 50.58 I-1 - J-1 measure 2669.47  
20" Catalpa Northeast 33.30

Replaced iron at the amended corner with an Allegan County Remonumentation iron and cap and accepted it as a careful and faithful perpetuation of the position of the original corner.

This corner was approved by the Allegan County Remonumentation Peer Group on December 9, 1997.

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 12-9-97  
COUNTY REP. K.V.O.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-1  
Allegan County Remonumentation iron and cap on the South line of Section 34, Town 5 North, Range 15 West at the amended corner. Azimuth = Michigan State Plane grid direction.
- |                                                                        |          |         |
|------------------------------------------------------------------------|----------|---------|
| I-13, Town 5 North, Range 15 West = Ottawa County Remonumentation iron | 90° 34'  | 111.90' |
| Allegan County Remonumentation tag in West side 18" Ash                | 346° 14' | 58.20'  |
| Allegan County Remonumentation tag in Southeast side power pole        | 65° 30'  | 82.70'  |
| Allegan County Remonumentation tag in East side twin 36" Oak           | 22° 16'  | 103.63' |
| Allegan County Remonumentation tag in North side power pole            | 108° 52' | 82.02'  |
| MSHD tag in Southeast side power pole                                  | 225° 02' | 51.99'  |
| Centerline East and West asphalt road pavement                         | 180°     | 2.50'   |
| Closing corner = 1/2" diameter bar in monument box                     | 179° 02' | 2.05'   |
| Centerline asphalt road pavement to South                              | 90°      | 13.50'  |

Signed by Steve Lampen Date DECEMBER 9, 1997

Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1976  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1983

REF 0006 PAGE 086

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

