

SURVEY & REMONUMENTATION

APR 07 1998

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Allegan

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|----------|------------------|
| 1. Public Land Survey | T4N R15W | ✓ I-13 SE corner |
| | T R | Section 34 |
| | T R | Fillmore Twp. |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

98 JAN 21 PM 1:22
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.
Stephen L. Lampen

98 JAN 21 PM 1:22

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Steven Lampen, in a field survey on December 29, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-13
GLO Lyon 1831
7" Cherry N 78 E 53
9" Birch N 73 W 15
Hicks, 1876
Stone

Consumers Power - 1968
Set iron
Street sign ESE 22.8'
Power pole NW 72.4'
Telephone pole SW 75.7'

Kirk L. VanOrder - 1986
Nail in top of flag post SW 62.15'
Centerline monument box W 58.85'
Centerline gas line marker NW 57.52'
Centerline Power pole NW 41.5'

Road Commission
PK in T.P. SW 70.0
Iron in field N 86.73
Iron in field NNE 164.02
PK in power pole NW 66.35
Jog West to Manlius cor. 59.23

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13
Found 3/4" iron in monument box
Centerline monument box W 58.85'
Centerline gas line marker post NW 57.52'
Centerline Power pole NW 41.5'


Replaced iron with 3/4"x24" Allegan County Remonumentation iron and remonumentation cap and accepted it as a careful and faithful perpetuation of the position of the original corner.

This corner was approved by the Allegan County Surveyors Peer Group on December 30, 1997.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 12-30-97
COUNTY REP. K.V.O.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13
Allegan County Remonumentation iron and cap in monument box Azimuth = Michigan State Plane grid
Remonumentation tag N face Power pole 76° 40' 143.80'
Remonumentation tag S face Power pole 104° 00' 139.46'
Remonumentation tag NNW face Power pole 245° 15' 69.74'
Remonumentation tag NNE face Power pole 318° 01' 41.71'
Southeast corner building, wood siding 325° 05' 256.68'
SE corner house, brick 286° 06' 446.44'
Centerline East and West asphalt pavement 180° 0.2'
Monument box 271° 01' 58.87'



Signed by Steven Lampen

Date DECEMBER 31, 1997

Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1982
ADAPTED FOR WORD PROCESSING MARCH, 1992