

SURVEY & REMONUMENTATION

APR 07 1998

ALLEGAN COUNTY REMONUMENTATION - LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Allegan (County) Located in: Corner Code #

1. Public Land Survey T4N R15W ✓ J-1
 T R
 T R
 T R
 T R

2. Property Controlling in Section S T R
 S T R
 S T R

3. Miscellaneous Property in Sec. S T R

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

98 JAN 21 PM 1:22
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
 FILED
 Register of Deeds Stamp & File Number

I, Steve Lampen, in a field survey on December 6, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3		2		1		
3													
4		7	8		9		10		11		12		
5													
6		18	17		16		15		14		13		
7													
8		19	20		21		22		23		24		
9													
10		30	29		28		27		26		25		
11													
12		31	32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 J-1 G.L.O. - corner not set by G.L.O. J-1 - Holland Engineering - 1993 5/8" iron Power pole North Northeast 95.67 Power pole West Southwest 188.70 Holland Township corner East 89.00 Centerline blacktop North 3.50
 J-1 MSHD - 1965 Set iron
 J-1 - I-1 = 2669.48
 J-1 - K-1 = 2668.93
 J-1 - J-13 = 89.00
 J-1 - J-3 = 5156.12


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 J-1 Found 5/8" iron
 J-1 - I-1 measure 2669.47 Power pole North Northeast 95.67
 J-1 - K-1 measure 2668.93 Power pole West Southwest 188.70
 J-1 - J-13 measure 88.96 centerline blacktop North 3.50
 J-1 - J-13 measure 5156.20

Found 5/8" iron on South line of Section 35, Town 5 North, Range 15 West, and replaced it with an Allegan County Remonumentation iron and cap. This position not monumented by the Original G.L.O. Survey. This monument is accepted as the best available evidence of the position of the corner.

Approved by the Allegan County Remonumentation Peer Group on December 9, 1997.
 Traversed 2647' on road.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 12-9-97
 COUNTY REP. K.V.O.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 J-1 Allegan County Remonumentation iron and cap on the South side of Section 35, Town 5 North, Range 15 West
 Azimuth = Michigan State Plane grid direction.
 Allegan County Remonumentation tag in East side power pole 2° 23' 95.67
 Allegan County Remonumentation tag in North side power pole 260° 48' 188.75
 Northwest corner house, foundation 232° 45' 422.21
 Northeast corner house, siding 230° 50' 410.80
 J-13, Town 5 North, Range 15 West = cast iron monument 90° 55' 88.96
 Centerline of the East and West asphalt road pavement 0° 3.50



Signed by Steven Lampen Date DECEMBER 12, 1997
 Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1976
 REVISED JAN., 1982
 ADAPTED FOR WORD PROCESSING MARCH, 1982