

# SURVEY & REMONUMENTATION

APR 07 1998

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan SECTION Located in: Corner Code #  
(County)

- |                                    |                            |               |
|------------------------------------|----------------------------|---------------|
| 1. Public Land Survey              | T <u>4</u> N R <u>15</u> W | ✓ K-6         |
|                                    | T ___ R ___                | W 1/4 Cor.    |
|                                    | T ___ R ___                | Sec. 13       |
|                                    | T ___ R ___                | E 1/4 Cor.    |
| 2. Property Controlling in Section | S ___ T ___ R ___          | Sec. 14       |
|                                    | S ___ T ___ R ___          | Fillmore Twp. |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___          |               |
|                                    | S ___ T ___ R ___          |               |

REGISTER OF RECORDS  
 ALLEGAN COUNTY, MI  
 98 JAN 21 PM 1:22  
 FILED  
*Joyce A. Carter*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kirk L. Van Order, in a field survey on June 9, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- K-6  
 (1) GLO Mar. 21, 1832, Calvin Britain, D.S.  
 North between Sec.s 13 & 14  
 40.00 ch. Set quarter Sec. post  
 Hemlock 14" South 27 links  
 Elm 18" N26°E 15 links  
 (2) County Surveyor notes, Oct. 24, 1879  
 Show stake at corner (no ties) (continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6  
 Kirk L. Van Order, P.C. Remon. survey dated June 9, 1997  
 Fd. 1/2" capped re-rod by using tie info. in Part A, Item No. 14. And is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer group approved June 10, 1997.

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 6-10-97  
 COUNTY REP. K.V.O.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- \*Note: Remon. iron to be set after road construction
- |   |               |           |
|---|---------------|-----------|
| K-5 A.C. Remon. iron                            | AZ 00°00'00"  | 2634.40'  |
| SE corner of red brick house                    | AZ 37°40'03"  | 243.57'   |
| SW corner of red brick house                    | AZ 26°34'15"  | 241.64'   |
| Nail & Remon. tag in N. side p. pole            | AZ 94°10'43"  | 76.30'    |
| C/L RR spike in Russcher Road                   | AZ 359°57'35" | 111.57'   |
| Fd. 3/4" steel rod in mon. box in Russcher Road | AZ 00°16'24"  | 109.65'   |
| Nail & Remon. tag in S. side p. pole            | AZ 265°09'43" | 136.35'   |
| K-7 fd. 3/4" iron pipe                          | AZ 180°13'00" | 2639.985' |

Signed by *Kirk L. Van Order* Date 12-31-97  
 Surveyor's Michigan License No. 23520

Section A (continued from Page 1)

K-6

Fillmore Twp., T.4N., R.15W.

- (3) D.A. Ratekin survey, July 6, 1971, L. 794, P. 92  
 Iron  
 St. sign S45°W 22.8'  
 N. end CMP N60°W 21.9'
- (4) D.A. Ratekin LCRC, July 29, 1971, L. 1, P. 93  
 1" Iron (same ties)
- (5) D.A. Ratekin survey, Dec. 30, 1975, L. 899, P. 389  
 1" Iron (same ties)
- (6) D.A. Ratekin survey, Aug. 18, 1977  
 1" Iron (same ties)
- (7) H.E.I. tie sheet, print out - received Jan. 31, 1997  
 1" iron (same ties)
- (8) K. Van Order survey, Dec. 29, 1982, L. 1027, P. 716  
 Fd. bent iron - removed and set capped iron  
 Power pole W,SW 135.95'  
 C/L Tele. cable box NW 99.35'  
 8" Apple NE 143.43'  
 10" Pear N,NE 175.22'
- (9) K. Van Order survey, Sept. 2, 1986, L. 1186, P. 174  
 Capped iron (same ties)
- (10) K. Van Order survey, Aug. 25, 1987, L. 1243, P. 06  
 Fd. Capped Iron (same ties)
- (11) Wightman-Moored tie info. Sept. 1, 1989  
 Fd. capped iron  
 Nail E. side power pole W,SW 135.95'  
 C/L Tele. box NW 99.35'  
 Nail E. Side Apple NE 143.43'  
 PK & Russcher Rd. N55°E+/- 98.10'  
 3/4" Iron in Mon. Box C/L Russcher N 109.6'  
 S 1/8 Post, NE 1/4 W 1349.5'
- (12) K. Van order survey, Nov. 28, 1989  
 Fd. capped iron  
 Power pole W,SW 135.95'  
 C/L Top tele. ped. NW 99.35'  
 11" Apple NE 143.43'  
 12" Pear N,NE 175.22'
- (13) K. Van Order survey, May 17, 1991  
 Fd. capped iron (same ties)
- (14) Kirk L. Van Order survey for A.C.R.C. dated Nov. 25, 1996  
 Fd. 1/2" capped re-rod  
 Fd. PK nail in N. side power pole E 76.43'  
 Set nail in S. side power pole W,SW 136.45'  
 C/L Top tele. ped. N,NW 99.35'  
 1" iron in mon. box  
 C/L Russcher Rd. N 110.67'