

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Allegan

<u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>15W</u>	<u>K-9</u>
	T ___ R ___	<u>Fillmore</u> Twp.
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBR0006 PAGE 72

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk L. Van Order, in a field survey on Apr. 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- K-9
(1) GLO
North between Sections 25 & 26
80.00 chains set post corner Sections 23, 24, 25 & 26
Beech 15" N65°E 9 links
Beech 6" N84°W 10 links
(2) J.W. Hicks, co. surveyor, Aug. 26, 1876
Stone with "x" on top (continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9
Fd. 3/4" x 36" steel well rod with joint in mon. box with the following witnesses:
Fd. nail & tag in NW side p. pole NE 47.60'
Fd. PK nail in SW side p. pole NW 64.43'
And is accepted as a careful and faithful perpetuation of the position of the original corner.
Peer group approved April 14, 1998.

APPROVED REMONUMENTATION CORNER
P.A. 343 OF 1990
ALLEGAN COUNTY
DATE APPROVED APRIL 14, 1998
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-9
Replaced found steel rod and set standard Allegan Co. Remon. monument (3/4" x 24" steel rod w/red cap #23520)
Nail & Remon. tag in NW side power pole AZ 48° 47.63'
Nail & Remon. tag in W side power pole AZ 174° 312.23'
Nail & Remon. tag in SW side power pole AZ 304° 64.47'
SE corner brick house AZ 343° 319.86'

Signed by: [Signature]
Surveyor's Michigan License No. 23520

Date APRIL 16, 1998



Section A (continued from page 1)

K-9

Fillmore Twp., T.4N., R.15W.

- (3) D.A. Ratekin Assoc., Inc. section corner witness card for Section 25
Fillmore Twp.
Boat spike over corner stone (rd. maps)
Power pole NE 36.3'
Guy pole NW 39.6'
St. sign SW 27.48'
Tel. pole SW
- (4) LCRC by Donald A. Ratekin in Liber 1, Page 299, dated Oct. 13, 1971
Part "A"
Old notes H.M. = stone E. end culvert SE 26.5'
W. end culvert SW 23'
Co. Rd. Comm. = bolt spike over stone
G.P. NW 39.74'
T.P. SE 38.11'
S. post 27.42'
Wit. iron NE 60.0'
Wit. iron SE 60.0'
Part "B"
Set 5/8" iron
Used iron witness NE & SE at 60'
To set corner back
Part "C"
5/8" iron 3' long
Iron 60.0' N45°E
Iron S45°E 60.0'
P. pole N45°E 35.9'
St. sign S45°W 42.7'
Guy pole N65°W 71.7'
- (5) LCRC by Donald A. Ratekin in Liber 1, Page 171, dated Dec. 1, 1971
Part "B"
Found Iron (destroyed during road construction)
Guy pole NW 39.74'
Tel. pole SE 38.11'
Sign post SW 27.42'
Part "C"
Set 1" iron
1/2" iron N45°E 60.00'
1/2" iron S45°E 60.00'
Tel. pole N60°W 71.74'
Power pole N45°W 35.88'
St. sign S40°W 42.72'
- (6) Kirk L. Van Order survey dated June 9, 1982
Fd. 3/4" iron bar in mon. box
Nail in sup. pole NW 64.43'
Nail in p. pole NE 47.60'