

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>15W</u>	<u>C-1 (NW Sec 5)</u>
	T _____ R _____	<u>Fillmore Twp.</u>
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	<u>Seg. #2</u>
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

97 JAN 22 FILE 1:22
 REGISTERED LAND SURVEYOR
 ALLEGAN COUNTY MICHIGAN

97 JAN 22 FILE 1:22

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David R. Greer, in a field survey on December 13, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-1	Government Notes	1831	Recorded in Liber 1, Page 134, Oct. 28, 1971
	Post		CL Manhole S45°W 34.00'
	Ironwood 5"	S46°E 10 links	CL Mon. Box N85°E 5.40'
	Beech 8"	S23°W 22 links	Recorded in Liber 2, Page 45, Nov 21, 1972
* NOTE:	This certificate supercedes the one recorded in Liber 4, Page 277, December 30, 1993 which contained an error.		MSHD Nail in Power Pole ENE 73.38'
			Traffic Light Guy Pole SW 39.17'
			Telephone Pole SE 68.33'
			Iron in Mon Box ENE 5.28'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1	Found 3/4" rod in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner		
Power Pole	NW	62.20'	APPROVED REMONUMENTATION CORNER
30" Maple	N	71.48'	P.A. 345 OF 1990
MSHD in Power Pole	ENE	73.38'	ALLEGAN COUNTY
Traffic light in Guy Pole	SW	39.17'	DATE APPROVED <u>3-9-94</u>
Iron in Mon Box	ENE	5.28'	COUNTY REP. <u>David R. Greer</u>
CL Manhole	S45°W	34.00'	

This closing corner is 0.91 South of the South line of Sec. 31, T5N, R15W



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 Replaced steel bar in monument box with A.C. Remonumentation Iron & Cap. AZ - Michigan State Grid Direction		
Iron in Mon Box C-13 SW Cor Sec 32 T5N R15W	AZ. 80°50'	5.28'
NE Cor Brick Building	AZ. 237°31'	76.68'
SE Cor Brick Building	AZ. 214°10'	127.51'
NW Cor Brick Foundation	AZ. 114°23'	143.01'
NE Cor Building Foundation	AZ. 107°33'	148.04'
SW Cor Building Foundation	AZ. 187°03'	189.98'
Fnd Nail & Tag N Side Power Pole	AZ. 70°00'	73.31'
Set O.C. Remon Nail & Tag E Side 30" Maple	AZ. 343°13'	71.39'
South line Sec 31, T5N, R15W	AZ. 359°41'10"	0.91'

Signed by David R. Greer Date 12/12/95
 Surveyor's Michigan License No. 16042

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983