

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>4</u> S. R. <u>16</u> E.	G-11
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ S. R. _____ E.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S. R. _____ E.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
 FILING NUMBER

DEC 7 1 05 PM '77
 REGISTERED SURVEYORS
 MICHIGAN COUNTY CLERK
 FILED

I, DONALD A. RATEKIN do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on DECEMBER 6, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

IN THE YEAR 1892 SURVEYOR FRED VAN LIENWEN AND CHAINMAN T. O. WILLIAMS FOUND AND SET THE FOLLOWING.
 AT CORNER OF SECTIONS 27, 28, 33, AND 34 WHERE FOUND SMALL STONE ON TOP OF REMNANTS OF OLD STAKE PUT IN IRON AND STONES.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

FOUND 1 1/2" IRON PIN WITH STONES AROUND, RAISED WITH 1/2" PIPE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" IRON PIPE OVER 1 1/2" IRON PIN
 NAIL IN NW SIDE 14" PINE N 70° E 92.23'
 NAIL IN SW SIDE 14" MAPLE N25°W 35.52'
 NAIL IN SW SIDE 30" MAPLE N65°W 45.39'
 NAIL IN WEST SIDE 6" MAPLE S10°E 22.54'
 FACE STREET SIGN N10°E 18.66'
 1 1/2" SQUARE IRON N9°W 11.8'
 WELL POINT S80°W 13.5'
 1 1/2" PIPE S12°W 8.0'


SIGNED BY Donald A. Ratekin DATE 12-6-77

SURVEYOR'S MICHIGAN REGISTRATION NO. 8781

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____