

## LAND CORNER RECORDATION CERTIFICATE

### FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 4 <u>X</u> R. 16 <u>X</u>	1-9 H-10
2. PROPERTY CONTROLLING IN SECTION 27	T. 4 <u>X</u> R. 16 <u>X</u>	5
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ S. R. _____	
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

18

FILED

MAY 4 10 56 AM '72

*Shirley A. ...*  
REGISTER OF DEEDS  
REGISTER OF DEEDS STAMP AND FILING NUMBER

I, DONALD A. RATEKIN do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on MARCH 27, 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19 found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

<p>1-9 GLU SET POST COR. SEC. 22, 23, 26, &amp; 27 BEECH 7 S49E 32 BEECH 10 N40W 8 OLD NOTES - IRON ST. SIGN 35.6' NW P. POLE SW 57.1' CARD-NW COR. STORE SE 63' - MAPLE 24" SW 38'</p>	<p>H-10 OLD NOTES - STONE - MAPLE 10" E 25.2 MAPLE 10" SE 42' CARD - STONE &amp; IRON 24" MAPLE NW 60.18</p>
---	--

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>1-9 3/4" PIPE</p>	<p>5 SET EQUAL DISTANCE &amp; STRAIGHT LINE BETWEEN N<sup>1</sup>/<sub>4</sub> POST &amp; CENTER OF SECTION.</p>	<p>H-10 5/8" IRON</p>
--------------------------	--	---------------------------

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>1-9 3/4" PIPE NW COR. STORE S45°E 62.80' ST. SIGN N45°W 35.52' P. POLE S45°W MSHD REF. NAIL 57.72' P. POLE N50°W 103.85'</p> <p><i>Rb 240 Rb 448</i></p>	<p>5 1" IRON 38" MAPLE S38°W 39.4' 1/2" IRON E 33.01' 32" MAPLE S45°E 34.9' 12" PINE N83°W 78.0'</p> <p><i>Rb 241 Rb 450</i></p>	<p>H-10 5/8" IRON 30" MAPLE E 24.24 TO NAIL FACING COR. 20" MAPLE S45°E 41.00 TO NAIL FACING COR. 24" MAPLE N30°W 60.11 TO NAIL FACING CORNER</p> <p><i>Rb 449 Rb 242</i></p>
---	--	---


SIGNED BY Donald A. Ratekin DATE 4-18-72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8781

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



*RAISE*