

ALLEGAN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners In
Allegan County

(County)	Located In:	Corner Code ##
	4N 16W	F-1 (N 1/4 Sec 4)
1. Public Land Survey	T ___ R ___	Laketown Twp.
	T ___ R ___	
	T ___ R ___	
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
David R. Greer

1993 DEC 30 PM 2:45

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, David R. Greer, in a field survey on September 13, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1 This corner not set by Government
Common corner to F-13, South 1/4, Sec. 33, T5N, R16W, Park Twp., Ottawa County This corner is shown in and fits the monument of Macatawa Park (Allegan & Ottawa County) Liber 2, Pages 12 and 18 and the monuments of Heneveld's Supervisor's Resubdivision of Macatawa Park (Ottawa County), Liber 9, Pages 32 and 33. This corner was recorded in Ottawa County with the following ties:
Set cast iron monument from ties & old plat as recorded in Liber 1, Page 809, Dec. 8, 1972.
40" Black Oak W 3.67' 30" Black Oak E 11.80'
10" Chinese Elm SW 7.46' 6" Beech NE 11.65'


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1
Found cast iron monument. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Set cast iron monument from ties & old plat as recorded in Liber 1, Page 809, Dec. 8, 1972.
40" Black Oak W 3.67'
30" Black Oak E 11.80'
10" Chinese Elm SW 7.46'
6" Beech NE 11.65'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1
Cast Iron Monument; Common Corner to F-13, S1/4, Sec. 33, T5N, R16W,
AZ - Michigan State Grid Direction
O.C. Remon tag & nail in S Side 42" Oak AZ. 245°48' 4.59'
O.C. Remon tag & nail in E Side 8" Beech AZ. 09°27' 12.02'
O.C. Remon tag & nail in N Side 6" Oak AZ. 94°52' 10.63'
O.C. Remon tag & nail in W Side 16" Beech AZ. 181°41' 30.87'
Fnd tag & nail #14091 S Side 16" Pine AZ. 238°98' 56.35'
Fnd iron pipe AZ. 304°25' 25.35'



Signed by David R. Greer Date 9/13/93
Surveyor's Michigan License No. 16042

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

W:\Data\Serv\Remon.dsc

LIBER 004 PAGE 344