

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ALLEGAN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T4N R16W	F-11
	T___ R___	S 1/4 COR. SEC. 28
	T___ R___	LAKETOWN TWP.
	T___ R___	
2. Property Controlling in Section	S___ T___ R___	
	S___ T___ R___	
3. Miscellaneous Property in Sec.	S___ T___ R___	
	S___ T___ R___	

REGISTERED
ALLEGAN COUNTY
97 JAN 22 PM 1:24
FILED
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ARTHUR W. BRINTNALL in a field survey on FEB. 9, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	H
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|---|
| F-11 GLO | 16 June 1904 (W&W Field Notes) |
| 40.00 Chains set qr. section post | 2,640' Set 1/4" corner on top of high ridge |
| Beech 14" S10W 24 links | 3,723' Set meander post per GLO |
| Beech 18" N31E 13 links | 3,853' Waters edge Lake Michigan |
| 56.41' Chains to Lake Michigan & Set Post | |

** (Continues on Back of Sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-11 This corner was re-established by measuring 2,640' along the monumented S. Line and is accepted as a careful and faithful re-establishment of the position of the original corner.

Approved by Allegan County Peer Group Date 3-12-96 APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 3-12-96
COUNTY REP. Rich L. Van Buren

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-11 Set 36" x 24" Steel pin with red plastic cap #23520 (Standard Allegan County Monument)
- East 7.19' 16-D and remon tag S side 12" Maple
- North 16.50' 16-D and remon tag W side 16" Beech
- N70°W 24.18' 16-D and remon tag S side 16" Oak (7.5 ± A/G)
- S10°E 12.92' 16-D and remon tag in NE root 22" Oak
- E 20' ± top of ridge



Signed by Arthur W. Brintnall Date MARCH 5, 1996
Surveyor's Michigan License No. PREIN & NEWHOF 28407

