

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
COMMISSION
Allegan (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>16W</u>	<u>F-13 (S-1/4 Sec-33)</u>
	T _____ R _____	<u>Laketown Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1993 DEC 30 PM 2:42
James A. Elliott
REGISTER OF DEEDS
ALLEGAN COUNTY, MICHIGAN
FILED
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David R. Greer, in a field survey on December 6, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Recorded in Liber 4, Page 53, May 3, 1989	F-13	Government Notes 1831
Set 1/2" Iron & Cap	Post	Tree 6" Unknown N37 1/2°E 2.09 chains
East Side 6" Poplar P.K.	N	26.81'
SE Side 6" Pine P.K.	NW	7.80'
SE Side 2" Pine P.K.	SSW	39.68'
S 44' ± centerline of trail		
1/2" Iron w/ cap N 1/4 cor Sec 4	E	20.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


F-13
Found 1/2" iron with cap and accepted it as a careful and faithful perpetuation of the position of the original corner

East Side 6" Poplar P.K.	N	26.81'
SE Side 6" Pine P.K.	NW	7.80'
SE Side 2" Pine P.K.	SSW	39.68'
S 44' ± centerline of trail		
1/2" Iron w/ cap N 1/4 cor Sec 4	E	20.00'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13
Replaced 1/2" Iron with Allegan County Remonumentation Iron & Cap

A.C. Remon tag & nail in N Side 6" Pine	W	13.41'
P.K. East Side 6" Pine	N	26.81'
P.K. SE Side 6" Pine	N40°W	7.80'
P.K. SE Side 2" Pine	S25°W	39.68'
Centerline Trail ±	S	44.00'
N 1/4, Sec 4, T3N R16W, Remon Iron & Cap	E	20.00'



Signed by David R. Greer Date 12/14/93
Surveyor's Michigan License No. 16042