

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

COM: For corners in

| | | |
|------------------------------------|--------------------------|-----------------------|
| Allegan (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>4N</u> R <u>16W</u> | <u>G-1 (NW-Sec-3)</u> |
| | T _____ R _____ | <u>Laketonw Twp.</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

1993 DEC 30 PM 2:22
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.
Register of Deeds Stamp & File Number

FILED

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, David R. Greer, in a field survey on November 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | |
|------------------|----------|---|
| Government Notes | 1831 | Recorded in Liber 1 Page 316 May 4, 1972 |
| Post | | These ties are to the closing corner. |
| Beech 12" S16°W | 20 links | The closing corner was 0.54 South of the Township line. |
| Beech 10" S60°E | 33 links | 1 1/4" diameter solid iron |
| | | CL: Ottogon Street |
| | | S 7.40' |
| | | 12" Maple |
| | | S20°W 61.80' |
| | | 28" Oak |
| | | S50°W 62.40' |
| | | Power Pole |
| | | S15°W 69.00' |
| | | 18" Maple |
| | | S75°E 76.20' |

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- G-1
Found 1" square iron in monument box at closing corner using the above witnesses and accepted it as a careful and faithful reestablishment of the original corner. Set Allegan County Remonumentation Iron and Cap on South line Section 33, Town 5 North, Range 16 West, 0.54 North of the closing corner. This iron fits the monumented corners of Macatawa Bay Addition, (square iron in monument box).

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-1
Set Allegan County Remonumentation Iron & Cap on South line, Section 33, T5N, R16W.
AZ = Michigan State Grid Direction
- | | | |
|--|----------------|---------|
| 1" square iron in monument box | AZ. 179°20'37" | 0.54' |
| Set A.C. Remon tag & nail in SW Side 14" Oak | AZ. 222°51' | 71.07' |
| SE Cor Metal Bldg. | AZ. 35°43' | 89.24' |
| SW Cor Metal Bldg. | AZ. 300°48' | 137.68' |
| A.C. Remon tag & nail in SW Side 16" Maple | AZ. 152°58' | 95.59' |
| G-13, SE Cor, Sec. 33, T5N, R16W, remon Iron & Cap | AZ. 89°22' | 124.66' |



Signed by David R. Greer Date 11/19/93

Surveyor's Michigan License No. 16042