

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
COMMISSION

Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>16W</u>	<u>H-1 (N-1/4 Sec-3)</u>
	T _____ R _____	<u>Laketown Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1993 DEC 30 PM 2:45
FILED
Sayer W. Chatter
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David R. Greer, in a field survey on November 19, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


H-1
Not set by the Government

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1
Found iron in monument box agrees with previous Section line measurements and surveys made by Holland Engineering, Inc. and by the subdivision "Huntington Estates", Liber 12, Page 56 (EXXEL Engineering) and is accepted it as a careful and faithful re-establishment of the position of the original corner. This iron is 4.21 South of the South line of Section 34, Town 5 North, Range 16 West. Set A.C. Remonumentation Iron & Cap at the intersection of the North and South 1/4 line of Section 3, with the South line of Section 34, Town 5 North, Range 16 West. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1 Allegan County Remonumentation Iron & Cap on S line of Section 34, T5N, R16W I	
AZ - Michigan State Grid Direction	
Iron in Monument Box	AZ. 180°00'50" 4.21'
O.C. Remon iron H-13 S1/4, Sec 34, T5N, R16W	AZ. 90°23' 98.18'
NE Cor Hse Foundation	AZ. 187°06' 80.71'
NW Cor Hse Foundation	AZ. 220°39' 107.08'
SW Cor Hse Foundation	AZ. 7°22' 88.71'
SE Cor Hse Foundation	AZ. 43°54' 123.11'
A.C. Remon tag & nail in NE Side 20" Maple	AZ. 148°27' 38.12'
SE Cor Hse Foundation	AZ. 309°27'137.60'



Signed by David R. Greer Date 11/19/93
Surveyor's Michigan License No. 16042

W:\Dca\Surv\Remon.doc

LIBER 004 PAGE 345