

ALLEGAN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MAR 16 1993
For corners in

Allegan County

Located In:

Corner Code #

- 1. Public Land Survey T ~~4N~~ R ~~16W~~ I-1 (NW Sec 2)
T R Laketown Twp.
- 2. Property Controlling S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

1993 DEC 30 PM 2:42
REGISTER OF DEEDS
ALLEGAN COUNTY, MICHIGAN
Singer, C. C. C. C.

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, David R. Greer, in a field survey on November 19, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Government Notes 1831 Post
Maple 36" S28°E 30 links
Beech 3" S76°W 19 links

A. Description of original monument and accessories and/or subsequent restoration:

I-1 Recorded in Liber 4 Page 20, March 13, 1987	Recorded in Liber 2, Page 246, Jan 14, 1974
1 1/2 inch iron pipe	Found 1 1/2" iron pipe
NW Cor Garage Foundation SE 101.93'	Ottawa Co. Cor E 107.08'
NE Cor House Foundation SW 109.52'	CL Street Sign SW 26.56'
SE Cor Bldg. Foundation NW 82.53'	Power Pole SW 36.26'
Nail in side of 20" Tree NW 71.65'	22" Ash NW 80.79'
FIP @ Se Cor Sec 34, T5N R16W E 107.08'	18" Oak NW 70.70'
1" Square Iron N 7.00' ±	Guy Pole NE 70.40'

These ties are to the closing corner. The closing corner was 0.32' S of the Township Line.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1
Found 1 1/2" square iron in monument box (closing corner) 0.32' South of Township Line using the above witnesses.
Set Allegan County Remonumentation Iron & Cap on South line Section 34, T5N, R16W, 0.32 North of closing corner
Accepted 1 1/2" square iron in monument box as a careful and faithful reestablishment of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A.C. Remonumentation Iron & Cap on S line, Sec. 34, T5N, R16W	AZ. 180°20' 0.32'
AZ - Michigan State Grid Direction	AZ. 90°03' 107.12'
1 1/2" square iron in mon. box (closing corner)	AZ. 133°03' 102.19'
D.C. Remon Iron I-3, SE Cor Sec 34, T5N R16W	AZ. 208°24' 109.83'
NW Cor Garage Foundation	AZ. 242°27' 81.71'
NE Cor House, Brick	AZ. 18°15' 74.76'
A.C. Remon tag & nail in S Side 18" Oak	
S'y cor Brick Pillar	



Signed by David R. Greer Date 12/14/93
Surveyor's Michigan License No. 16042

W:\Deed\Serv\Remon\Jec

LIBER 004 PAGE 284

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1985