

REMONUMENTATION

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

Allegan (County) Located In: Corner Code #

1. Public Land Survey	T <u>4N</u> R <u>16W</u>	<u>1-2 W 1/4 Cor</u>
	T _____ R _____	<u>Sec 2</u>
	T _____ R _____	<u>Laketown Twp.</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1994 DEC 30 PM 12:16
 Register of Deeds
 ALLEGAN COUNTY MICHIGAN

FILED

Register of Deeds Stamp & File Number

I, John P. Clapp, in a field survey on December 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-2 General Land Office Survey Notes, 1831 Lucius Lyon, Surveyor Set Post 9" Beech S85°E 26 links 7" Beech N40°W 3 links	I-2 Recorded in Liber 2, Page 246, Jan 14, 1974 Fd Iron on Stone Cor Headwall NE 27.4' Cor Headwall SW 27.2' Cor Headwall SE 29.0' 28" Maple NE 46.0' 24" Maple NW 54.1'	I-2 Recorded in Liber 3 Page 303, May 18, 1981 Iron Pipe in Mon. Box 42" Maple NE 45.64' 24" Maple NW 54.18' Power Pole NE 63.82' Guy Pole SW 45.40'
--------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	---------------------------------------------------------------------------------------------------------------------------------------------------------------------

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


I-2
Found bolt in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner.
Found Nail & Tag in SW Side Power Pole AZ 58° 63.78'
Found P.K. Nail in S Side 42" Maple AZ 49° 46.51'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 12-13-94
COUNTY REP. John P. Clapp

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-2 Set A.C. Remon Cap & Iron in Monument Box	AZ. 260°	195.67'
A.C. Remon Tag & Nail in E Side 24" Maple	AZ. 161°	92.10'
A.C. Remon Tag & Nail in E Side 12" Maple	AZ. 104°	117.32'
A.C. Remon Tag & Nail in S Side 36" Beech	AZ. 218°	118.61'
SE Corner Brick Siding on Garage	AZ. 59°	85.11'
SW Corner Garage Foundation House #4703		

Signed by John P. Clapp Date Dec 12, 1994
Surveyor's Michigan License No. 14091



I-2 Old County Surveyor Records
 Show "stone" (no date)
 Beech SE 43.6'
 Maple NE 45.7'

I-2
 Old County Surveyor Records
 Show "S. & iron" (no date)
 18" Maple NE 46.2'
 30" Beech SE 44.2'
 12" Apple SW 63'

I-2
 Recorded in Liber 3, Page 334
 June 9, 1982
 Iron in Monument Box
 42" Maple NE 45.64'
 24" Maple NW 54.18'
 Power Pole NE 63.82'
 Guy Pole SW 45.40'

REPRODUCED FROM THE ORIGINAL RECORDS OF THE
 SURVEYOR GENERAL'S OFFICE
 ALTHOUGH THE ORIGINAL RECORDS ARE
 DEPOSITED IN THE STATE ARCHIVES
 THIS REPRODUCTION IS THE PROPERTY OF THE
 SURVEYOR GENERAL'S OFFICE