

REMONUMENTATION

APR 25 1995

COMMISSION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
ALLEGAN COUNTY MICHIGAN
 1994 DEC 30 PM 12:15
 FILED

Allegan County Located in: Corner Code #
 1. Public Land Survey T 4N R16W I-10 W1/4 Cor
 T R Sec 26
 T R Laketown Twp.
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	15	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John P. Clapp, in a field survey on December 5, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 I-10 County Surveyor records show "iron & stone" (no date, no witnesses)
- | | | |
|---|---|--|
| I-10 Gen Land Office Survey Notes
1832-Surveyor, Lucius Lyon
Set Post
6" Beech N75°E 14 links
12" Beech N45°W 4 links | I-10 Recorded in Liber 1,
Page 146, Oct 28, 1971
Fd 1" Iron, Stake & Stone
14" Tw Cherry S30°E 87.20'
T. Pole S20°E 96.40'
14" Maple S40°W87.50' | I-10 Recorded in Liber 4
Page 16, March 13, 1987
Fd. 1" Iron
20" Cherry S30°E 88.03'
20" Maple S40°W87.96'
Tw. Cherry NW 91.28'
10" Pine NE 97.85' |
|---|---|--|


- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- I-10
 Found 1" iron pipe in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner.
 Found Nail in N Side 12" Pine AZ 79° 97.72'

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 12-13-94
 COUNTY REP. And. L. Van Ouden

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-10
 Set A.C. Remon Cap & Iron in Concrete in Monument Box
- | | | |
|---|----------|---------|
| A.C. Remon Tag & Nail in SE Side 14" Oak | AZ. 18° | 140.85' |
| A.C. Remon Tag & Nail in N Side 6" Pine | AZ. 131° | 62.96' |
| A.C. Remon Tag & Nail in SE Side 8" Oak | AZ. 225° | 110.06' |
| A.C. Remon Tag & Nail in SW Side 8" Tw Cherry | AZ. 302° | 76.50' |

Signed by John P. Clapp Date Dec. 6, 1994
 Surveyor's Michigan License No. 14091



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, 1971
 REVISIONS: 14, 1975
 REGISTERED LAND SURVEYOR, JAN., 1982

W:\Docst1\Surv\Remon.doc

0005 PAGE 093