

**SURVEY
REMONUMENTATION**

APR 25 1995

COMMISSION

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 30 PM 12:17
Register of Deeds Stamp & File Number

FILED

Located in: Allegan (County) Corner Code # _____

1. Public Land Survey T 4N R 16W J-9 N1/4 Cor
 T _____ R _____ Sec 26
 T _____ R _____ Laketown Twp.
 T _____ R _____ _____
 T _____ R _____ _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

I, John P. Clapp, in a field survey on December 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
12												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-9 Gen: Land Office Survey Notes 1831 Lucius Lyon, Surveyor Set Post 8" Beech N1°W 10 links 4" Beech S15°W 7 links	J-9 Recorded in Liber 2, Page 380, Apr. 14, 1975 Fd 3/4" pipe from Co. ties MDSH r/w mon SSE 86.29' Fence Post SW 30.60' Power Pole NNW 58.57'	J-9 Recorded in Liber 3 Page 60, Feb 25, 1976 3/4" Pipe in CL Asphalt Fence Post S35°W 30.59' Power Pole N20°E 58.55' NW cor r/w mon S30°E 86.00'
--	---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


J-9 Found 1" steel bar in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner.
 Found Nail in SW Side Power Pole AZ. 17° 58.66'
 Found Nail & Tag in SE Side Fence Post AZ. 205° 30.67'
 C/L of Top of MDSH r/w Mon AZ. 149° 86.28'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 12-13-94
COUNTY REP. John P. Clapp

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9 Set A.C. Remon Cap & Iron in Monument Box	AZ. 21°	321.97'
SE Corner Garage	AZ. 84°	225.09'
A.C. Remon Tag & Nail in S Side 16" Triple Tree	AZ. 176°	404.25'
A.C. Remon Tag & Nail in W Side Tree	AZ. 247°	88.10'

Signed by John P. Clapp Date Dec. 8, 1994
 Surveyor's Michigan License No. 14091



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISIONS MAY 14, 1975
 REVISED JAN., 1983

0005 PAGE 124

J-9
Michigan State Highway Department
July 19, 1967
Found 3/4" pipe in CL 140th Avenue
and Consumers Power Line
Power Pole N20°E 58.55'
Telephone Pole S45°E 41.40'
R/W Monument S30°E 86.00'

RECORD OF SURVEY
IN
MICHIGAN
STATE HIGHWAY DEPARTMENT
JULY 19, 1967