

REMONUMENTATION

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

Register of Deeds
ALLEGAN COUNTY MICHIGAN
Joyce A. Blanton

1994 DEC 30 PM 12: 17

FILED

Allegan (County) Located in: Corner Code #

1. Public Land Survey T 4N R 16W J-10 Center
 T _____ R _____ Sec 26
 T _____ R _____ Laketown Twp.
 T _____ R _____ _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, John P. Clapp, in a field survey on December 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-10 This position not established by original Government Surveyors.
 Recorded in Liber 3, Page 306, April 16, 1981
 2" Pipe in CL of old grade at the intersection of the 1/4 lines
 Power Pole SE 31.40'
 Consumers Power Co. pipe above ground NE 31.90'
 Consumers Power Co. pipe above ground NW 34.40'
 5.5' S of line between Cons. Power Co. Pipes

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 12-13-94
 COUNTY REP. Paul A. Van Orden

J-10
 Found 2" iron pipe in centerline of old grade at the intersection of 1/4 lines
 Power pole SE 31.40'
 Consumers Power pipe above ground NW 34.40'
 This position not established by original Government Surveyors. This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-10
 Found 2" Pipe. Set Allegan County Remonumentation Iron & Cap at intersection of 1/4 lines
 A.C Remon Tag & Nail in SW Side Power Pole AZ. 153° 32.13'
 A.C. Remon Tag & Nail in SE Side 6" Oak AZ. 289° 25.88'
 A.C. Remon Tag & Nail in SE Side 8" Maple AZ. 221° 41.40'
 A.C. Remon Tag & Nail in N Side 8" Oak AZ. 103° 59.03'
 A.C. Remon Tag & Nail in SW Side 4" Oak AZ. 318° 36.26'

Signed by John P. Clapp *John P. Clapp* Date Dec 8, 1994
 Surveyor's Michigan License No. 14091



W:\Docs\Surv\Remon.doc
 Traverse on road 1320'
 Traverse off road 9225'

J-10 State Plane Grid Azimuth

K-10	AZ 91-14-42	2635.068'
J-11	AZ 179-19-53	2618.336'
I-10	AZ 271-14-42	2641.751'
J-9	AZ 359-19-53	2649.689'

APPROXIMATE STATE PLANE GRID AZIMUTHS
FOR THE SECTIONS SHOWN ON THIS MAP
DATED 1950
COUNTY HERBERT, ARIZONA