

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan (County)

1. Public Land Survey	T <u>4N</u> R <u>16W</u>	<u>K-1 (NW Cor - Sec 1)</u>
	T _____ R _____	<u>Laketown Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1993 DEC 30 PM 2:42
James A. LeBlanc
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
FILED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	15	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David B. Greer, in a field survey on September 13, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-1						
Government Notes 1831				Recorded in Liber 2, Page 85, Dec. 18, 1972		
Post				"T" iron over iron pipe	S50°W	3.00'
Beech 7"	S40°E	24 links		SW Cor House	N30°W	39.60'
Beech 8"	S36°W	9 links		SE Cor House	N5°E	33.00'
				Street Sign	S45°W	48.80'
				Power Pole	S50°E	37.30'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1
 Found steel bar in monument box on South line of Township (S line Sec 35, T5N, R16W). The above witnesses fit the closing corner which is 1.92' North of the Township line. Set Allegan County remonumentation iron & cap on Township line 1.92' South of closing corner and accepted it as a careful and faithful reestablishment of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1						
Set A.C. Remonumentation iron & cap on S line Sec 35, T5N, R16W						
AZ = Michigan State Grid Direction						
Steel bar (closing corner)	AZ.	0°43'	1.82'			
SE Cor House Foundation	AZ.	02°39'	34.82'			
NW Cor House Foundation	AZ.	233°30'	124.38'			
NE Cor House, Brick	AZ.	133°47'	134.08'			
SW Garage Cor Foundation	AZ.	309°35'	79.54'			
O.C. Remon Iron & Cap K-13	AZ.	80°08'	75.08'			
(SW cor, Sec 35, T5N R16W)						



Signed by David R. Greer Date 9/13/93

Surveyor's Michigan License No. 16042
 LIBER 004 PAGE 283