

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1995 DEC 14 PM 2:34  
ALLEGAN COUNTY REGISTER OF DEEDS

FILED

For corners in  
Allegan (County) Located in: Corner Code #

1. Public Land Survey T4N R16W K-2  
T R W 1/4 Cor.  
T R Sec. 1  
T R E 1/4 Cor.  
T R Sec. 2  
T R Lakeroun Twp.

2. Property Controlling in Section S T R  
S T R  
S T R

3. Miscellaneous Property in Sec. S T R  
S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

SURVEY & MONUMENTATION  
APR 29 1995  
COMMISSION

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Steven Lampen, in a field survey on March 23 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-2 GLO - Dec. 1832 Calvin Britain Set 1/4 sec. post 4" Beech S 74° E 20' 20" Hemlock N 74° W 30'	K-2 LCRC L 1-P 313 1972 St. sign N 45° E 37.1' P. pole N 65° W 84.4' P. pole S 40° E 52.8' Found 1/2" pipe	K-2 LCRC L 2-P 41 1972 Nail in P. pole NW 84.71' Nail in fence post NW 45.07' Nail in P. pole SE 53.15' Street sign post NE 37.12'
	K-2 LCRC L 2-P 90 1973 Found 3/4" pipe in Mon. box Centerline street sign P. pole P. pole	NE 37.20' SE 52.60' NW 84.40'

K-2  
KVO Survey  
Found 1" steel rod in Mon. box  
P. pole SE 53.28'  
Corner fence post NW 56.35'  
P. pole NW 84.61'  
Corner fence post NE 41.52'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-2  
Found 1 1/4" iron, 3/4" pipe, drag tooth and stone in Mon. box and is accepted as a careful and faithful perpetuation of the position of the original corner.

P. pole N 65° W 84.4'	Nail in P. pole NW 84.71'	P. pole SE 53.28'	P. pole SE 52.60'
P. pole S 40° E 52.8'	Nail in P. pole SE 53.15'	corner fence post NW 56.35'	P. pole NW 84.40'
		P. pole NW 84.61'	

APPROVED REMONUMENTATION CORNER

P.A. 345 OF 1990  
ALLEGAN COUNTY

DATE APPROVED 11-14-95  
COUNTY REP. Rich L. Van Orden

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2  
Found iron in mon. box and set Allegan County Remonumentation iron and cap in mon. box.  
AZ = MI State plane grid direction

P. pole Remon. tag NE side	145° 28'	53.27'
SW corner garage foundation	114° 25'	399.93'
SE corner house, brick	333° 47'	324.30'
SW corner house, siding	327° 44'	344.55'
P. pole, Remon. tag S side	292° 01'	84.54'



Signed by Steven Lampen

Date November 14, 1995

Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 25, 1977  
REVISED MAY 14, 1978  
REVISED JAN., 1982  
ADAPTED FOR WORD PROCESSING MARCH, 1982