

REMONUMENTATION

APR 25 1995

COMMISSION

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 30 PM 12:17  
Register of Deeds  
ALLEGAN COUNTY MICHIGAN  
*James A. Blanton*

FILED

Located In: Allegan County

Corner Code #  
L-3 N1/4 Cor  
Sec 12  
Laketown Twp.

1. Public Land Survey T 4N R 46W  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John P. Clapp, in a field survey on December 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-3 Gen. Land Office Survey Notes 1831 Lucius Lyon, Surveyor Set Post 3" Ironwood N46°E 3 links 4" Sugar S31°W 14 links	L-3 Recorded in Liber 1, Page 54, June 4, 1971 3/4" rod in mon box NW Cor Br Hse S45°E 111.5' NW Cor Br. Fnd S45°W 112.5'	L-3 Recorded in Liber 1 Page 313, May 4, 1972 1" Iron Power Pole S45°E 49.5' Power Pole N45°W 38.9' Street Sign N30°E 40.8'
--	---	--

(See reverse side for additional recordings 1, 2, P. 47)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3  
Found 1" pipe in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner.

NW Cor Brick House	AZ. 137°	111.51'
NW Cor Foundation	AZ. 225°	113.28'
Found P.K. Nail W Side Light Pole	AZ. 314°	39.31'
Found P.K. Nail SW Side Power Pole	AZ. 135°	50.15'
NW Cor Conc. Slab	AZ. 36°	75.59'
SW Cor Conc. Slab	AZ. 43°	66.41'

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 12-13-94  
COUNTY REP. John P. Clapp


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3  
Set A.C. Remon Iron and Cap in Monument Box  
A.C. Remon Tag & Nail in SW Side Power Pole  
NW Corner Concrete Slab for Lift Station  
NE Corner Brick Garage  
NW Corner Foundation House #6104

AZ. 314°	39.47'
AZ. 36°	75.59'
AZ. 120°	170.96'
AZ. 225°	113.28'

Signed by John P. Clapp  
Surveyor's Michigan License No. 14091

Date Dec 13, 1994



W:\Docs\Surv\Remon.doc

LIBER 0005 PAGE 132

PAGE 1 of 2

L-3

Recorded in Liber 2, Page 47, Oct. 11, 1972

Found Monument Box		
8" Apple	SW	61.90'
10" Apple	SW	66.75'
12" Apple	SW	80.10'
Power Pole	SE	49.80'
Power Pole	NW	39.0'

L-3

Unrecorded ties from Prein and Newhof

Power Pole	NW	39.27'
Power Pole	SE	50.10'
NW Cor Conc Slab	NE	75.56'
SW Cor Conc Slab	NE	66.50'

RECORDED IN LIBER 2, PAGE 47, OCT. 11, 1972

DEPARTMENT OF REVENUE

STATE OF MISSISSIPPI

