

SURVEY & REMONUMENTATION

APR 25 1995

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

COMMISSION

Allegan (County)

Located In: Corner Code #

- 1. Public Land Survey T 4N R 16W L-9 N1/4 Cor
T _____ R _____ Sec 25
T _____ R _____ Laketown Twp.
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

1994 DEC 30 PM 12:15
REGISTER OF DEEDS
ALLEGAN COUNTY MICHIGAN
James A. Clapp

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 16 | 17 | 18 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, John P. Clapp, in a field survey on December 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | |
|---|--|---|
| L-9 Gen Land Office Survey Notes 1831 Lucius Lyon, Surveyor Post 11" Hemlock W 10 links 12" Beech S70°E 20 links | L-9 Recorded in Liber 4, Page 17, March 13, 1987 3/4" iron in mon box NE Cor Hse Stone SW 133.55' SE Cor Hse Brick NE 134.62' SW Cor Gar Brick NNE 98.70' | L-9 Recorded in Liber 2 Page 240, Nov. 28, 1973 PK Nail T. Pole N20°W 30.57' 4" Maple N55°W 90.16' PK Nail 10" Sass. S25°W 98.45' NE Cor Hse S70°W 133.60' |
|---|--|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9
Found 3/4" iron in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner

| | | |
|----------------------------|----------|---------|
| NE cor stone house #6106 | AZ. 242° | 133.57' |
| SE Cor Brick House #6099 | AZ. 44° | 134.65' |
| SW Brick Gar.; House #6099 | AZ. 12° | 98.75' |

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 12-13-94
COUNTY REP. *Keith A. Van Orden*


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9

| | | |
|---|----------|---------|
| Set A.C. Remon Cap & Iron in Monument Box | | |
| SW Cor Brick House #6099 | AZ. 12° | 98.75' |
| SE Cor Brick House # 6099 | AZ. 44° | 134.65' |
| A.C. Remon Tag & Nail in E Side 14" Sassafras | AZ. 188° | 98.35' |
| NW Cor Brick Porch; House #6106 | AZ. 248° | 147.85' |
| SW Cor Brick; House #6105 | AZ. 309° | 154.15' |

Signed by John P. Clapp *John P. Clapp*
Surveyor's Michigan License No. 14091

Date Dec. 8, 1994



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 2, 1971
14091 REVISOR 8-14-1975
REGISTERED LAND SURVEYOR, MICH. 1983

W:\Docs\Sun\Remon.doc

USER 0005 PAGE 094