

# REMONUMENTATION

APR 25 1995

## COMMISSION

For corners in

### ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Register of Deeds  
 ALLEGAN COUNTY MICHIGAN  
*James A. Clapp*

1994 DEC 30 PM 12:17

FILED

Allegan _____ <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>16W</u>	<u>L-10 Center</u>
	T _____ R _____	<u>Sec 25</u>
	T _____ R _____	<u>Laketown Twp.</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John P. Clapp, in a field survey on December 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 L-10 This position not established by original Government Surveyors


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 L-10  
 Set Allegan County Remonumentation Iron and Cap at the intersection of quarter lines. This position not established by original Government Surveyors. This monument is accepted as the best available evidence of the position of the corner.

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 12-13-94  
 COUNTY REP. *Rich. R. Van Orden*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 L-10  
 Set Allegan County Remonumentation Iron & Cap at intersection of 1/4 lines

A.C. Remon Tag & Nail in SW Side 6" Poplar	AZ.	154°	11.98'
A.C. Remon Tag & Nail in N Side 6" Poplar	AZ.	82°	9.70'
A.C. Remon Tag & Nail in E Side 10" Maple	AZ.	351°	23.25'
A.C. Remon Tag & Nail in N Side 36" Maple	AZ.	302°	19.95'
CL N-S Ditch	AZ.	W	8'
CL Ditch to West	AZ.	S	5'

Signed by John P. Clapp *John P. Clapp* Date Dec. 8, 1994  
 Surveyor's Michigan License No. 14091



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JUL. 28, 1971  
 REVISION MAY 14, 1975  
 REVISED JAN., 1983

W:\Doc1\Surv\Remon.doc  
 Traverse on road 3320'  
 Traverse off road 7327'

L-10 State Plane Grid Azimuth

M-10	AZ 90-58-22	2701.107'
L-11	AZ 179-26-24	2632.320'
K-10	AZ 270-58-22	2673.031'
L-9	AZ 359-26-24	2640.389'

89.400

1000