

REMONUMENTATION

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Allegan	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>4N</u> R <u>16W</u>	<u>L-11 N1/4 Cor</u>
	T _____ R _____	<u>Sec 36</u>
	T _____ R _____	<u>Laketown Twp.</u>
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

1991 DEC 30 PM 12:15
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
James A. Clapp

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John P. Clapp, in a field survey on December 6, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | |
|---|----------------------------------|--------------------------|
| L-11 Gen. Land Office Survey Notes | L-11 Recorded in Liber 1, | L-11 Recorded in Liber 2 |
| 1832-Surveyor, Lucius Lyon | Page 173, Jan 6, 1972 | Page 387, June 19, 1975 |
| Set Post | Replaced iron destroyed | Fd Steel Rod in Mon. Box |
| 20" Hemlock N62°W 28 links | during road construction | St. Sign S20°E 21.85' |
| 9" Hemlock N79°E 17 links | Hub N25°W 71.71' | Stop Sign N10°W 44.95' |
| L-11 | Hub S41°W 53.30' | CL W End CMP 33.35' |
| No old County Surveyor records exist for this corner. | 4" Cherry N18°E 71.18' | CL E End CMP 43.00' |
| | 5/8" iron rods N 100' & 200' | |
| | 5/8" iron rods N45°W 100' & 175' | |

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-11
 Found 1/2" x 18" square bolt in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner.
 Found 5/8" Iron AZ. 00° 100.13' (bent)
 Street Sign AZ. 148° 21.89'
 Stop Sign AZ. 347° 44.90'
 CL West End CMP AZ. 330° 33.20'
 CL East End CMP AZ. 48° 42.72'
 Found Nail in E Side 6" Pine AZ. 203° 47.17'

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 12-13-94
 COUNTY REP. Mark A. Van Oort

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-11
 Set A.C. Remon Cap & Iron in Concrete in Monument Box
 A.C Remon Tag & Nail in E Side 6" Poplar AZ. 39° 55.93'
 A.C. Remon Tag & Nail in W Side 8" Pine AZ. 188° 38.63'
 NW Corner Foundation of House #6102 AZ. 222° 137.05'
 A.C. Remon Tag & Nail in SW Side 8" Sassafras AZ. 297° 116.36'

Signed by John P. Clapp *John P. Clapp* Date Dec 7, 1994
 Surveyor's Michigan License No. 14091

