

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

| For corners in <u>Allegan</u> (County) | Located In: | Corner Code # |
|--|---|---|
| 1. Public Land Survey | T4N R16W T _____ R _____ T _____ R _____ T _____ R _____ | M-2 E 1/4 cor. Sec. 1 Laketown Twp. |
| 2. Property Controlling in Section | S _____ T _____ R _____ S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

1995 DEC 14 PM 2:34
REGISTER OF DEEDS
FILED

**SURVEY &
REMONUMENTATION
COMMISSION**

APR 29 1996

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Steven Lampen, in a field survey on March 23, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | | |
|-----------------------|-------------------------|--------------------|-----------|
| M-2 | LCRC L 1-P 302 | LCRC L 2-P 47 | |
| GLO - 1832 | 1" pipe | Found 1" iron pipe | |
| Lucius Lyon | | Centerline hydrant | NE 58.10' |
| Set 1/4 sec. post | St. sign S 60° E 27.6' | St. sign | SE 27.6' |
| 24" Beech S 10° W 4' | 14" Maple N 30° E 73.2' | 14" Maple | NE 73.2' |
| 10" Beech N 51° W 29' | 24" Maple N 40° W 49.3' | SE corner porch | NW 90.13' |
| | | Iron | N 16.12' |

KVO survey
Found 1 1/4" pipe in Mon. box
NW corner house SE 87.00'
Centerline Tel. ped. SW 45.65'
NE corner house NW 106.10'
23" Maple NE 73.74'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2
Found 3/4" pipe in Mon. box and accepted it as a careful and faithful perpetuation of the position of the original corner.

| | | | | |
|-------------------------|--------------------|-----------|----------------------|------------|
| 24" Maple N 40° W 49.3' | Centerline hydrant | NE 58.10' | NW corner house | SE 87.00' |
| | SE corner porch | NW 90.13' | Centerline Tel. Ped. | SW 45.65' |
| | Iron | N 16.12' | NE corner house | NW 106.10' |


Approved by Allegan County Remonumentation Peer Group, November 14, 1995

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 11-14-95
COUNTY REP. *Neil L. ...*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2
Found 3/4" pipe in Mon. box and set Allegan County Remonumentation iron and cap in Mon. box

| | | |
|-------------------------------------|------------|---------|
| M-1, T4N, R16W | 0° 19' 05" | 2542.2' |
| A-2, T4N, R15W | 0° 19' 05" | 16.215' |
| NW corner house foundation | 123° 34' | 87.10' |
| NE corner house foundation | 224° 44' | 106.92' |
| Centerline top of hydrant | 25° 18' | 58.69' |
| 12" Maple, remon. tag NW side | 53° 59' | 97.20' |
| SE corner concrete block porch wall | 312° 45' | 90.90' |



Signed by Steven Lampen Date November 14, 1995
Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
REVISED MAY 16, 1975
REVISED JAN. 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983