

# SURVEY & REMONUMENTATION

APR 25 1995

## ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

Allegan (County)

Located In:

Corner Code ~~##~~

1. Public Land Survey

T 4N R 16W

M-10-E1/4 Cor

T \_\_\_ R \_\_\_

Sec 25

T \_\_\_ R \_\_\_

Laketown Twp.

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1994 DEC 30 PM 12:16  
REGISTER OF DEEDS  
ALLEGAN COUNTY MICHIGAN  
*James A. Bette*

FILED

Register of Deeds Stamp & File Number

I, John P. Clapp, in a field survey on December 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
12												
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-10 Gen: Land Office  
Survey Notes 1831  
Lucius Lyon, Surveyor  
Set Post  
7" Cherry N33°W 19 links  
6" Beech S58°W 33 links

M-10 Recorded in Liber 3, Page 194  
Set 1/2" steel rod from records of County Surveyor  
NE Corner Porch S30°W 109.64'  
24" Butternut W 40.53'  
Power Pole S60°E 58.12'  
NE Corner House S70°E 118.17'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10  
Found 1/2" steel bar in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner.  
NE Corner Porch  
Nail S Side 24" Butternut AZ. 225° 109.65'  
Nail SW Side Power Pole AZ. 266° 40.78'  
AZ. 135° 53.99'

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 12-13-94  
COUNTY REP. *Keith A. Van Orden*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10  
Set A.C. Remon Cap & Iron in Monument Box  
A.C. Remon Tag & Nail in S Side 34" Hickory AZ. 82° 232.99'  
NE Cor Foundation; House # 3897 AZ. 116° 116.18'  
A.C. Remon Tag & Nail in W Side 40" Maple AZ. 165° 112.05'  
NW Corner Garage Foundation AZ. 242° 153.48'  
A.C. Remon Tag & Nail in SW Side 17" Pear AZ. 332° 147.66'  
A-10, T4N, R15W AZ. 180° 3.30'

Signed by John P. Clapp

*John P. Clapp*

Date Dec. 8, 1994

Surveyor's Michigan License No. 14091

W:\Docs\Surv\Remon.doc

18FR0005 PAGE 096

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS - JAN. 26, 1971  
SURVEYOR NO. 14091 RENEWED MAY 14, 1979  
REGISTERED LAND SURVEYOR REVISED JAN., 1983

