

**Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

COPIES

97 JAN 22 PM 1:25
REGISTERED SURVEYOR
ALLEGAN COUNTY, MICH.
FILED

For corners in <u>Allegan</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T3N R15W	* A-1 (NW, Sec. 6)
	T R	Marius Twp.
	T3N R16W	M-1 (NE, Sec. 1)
	T R	Saugatuck Twp.
2. Property Controlling in Section	S T4N R16W	* M-13 (SE, Sec. 36)
	S T R	Laketown Twp.
3. Miscellaneous Property in Sec.	S T4N R15W	A-13 (SW, Sec. 31)
	S T R	Fillmore Twp.
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Steven Lampen, in a field survey on December 10, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-1 GLO - L. Lyon 1831 Beech 6 N 8 W 4 Sugar 10 S 10 W 5 Road Commission P.K. in power pole NE 78.60' P.K. in power pole ESE 114.70' P.K. in power pole SW 151.31' Face of 7" Maple SE 92.00' P.K. in pavement N 100' & 200'	County Notes Found 1 3/4" pipe 1967 Street sign SW 34.6' Stop sign NW 41.5' Power pole NE 78.0' Telephone pole SE 48.3' NW corner garage SE 147.85'	Kirk VanOrder, 1991 Survey Capped iron in monument box Telephone pole SE 48.44' Power pole ESE 114.56' NW barn corner SE 123.20' Power pole SW 151.31' Power pole NE 78.48'
	County Records - 1924 12" Elm SE 59.2' SE corner headwall NE 32.8' SW corner headwall NW 32.8'	Kirk VanOrder, 1980 Survey Set P.K., P.K. power pole NE 78.60', P.K. power pole ESE 114.70', P.K. power pole SW 151.31', face 7" Maple 92', centerline monument box NE 0.65'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1 Found capped iron in monument box Face 7" Maple SE 92' P.K. power pole NE 78.60' P.K. power pole ESE 114.70' Telephone pole SE 48.44' Power pole ESE 114.56' NW barn corner, SE 123.20'	Power pole SW 151.31' Power pole NE 78.48' Telephone pole SE 48.44' Power pole WNW 135.30' Power pole SW 151.65' Power pole NE 78.0' Telephone pole SE 48.3'
---	---

Replaced capped iron with 3/4"x24" Allegan County Remonumentation iron and cap and is accepted as a careful and faithful perpetuation of the original corner.


This corner approved by Allegan County Surveyors Peer Group on December 10, 1996

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 12-10-96
COUNTY REP. Paul J. VanOrder

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1
3/4"x24" Allegan County Remonumentation iron and cap in monument box in centerline asphalt road in section.
AZ = Michigan State Plane grid direction

Power pole Remon. tag and nail N'ly side	18° 28'	78.49'
Power pole Remon. tag and nail S'ly side	304° 11'	135.21'
Power pole Remon. tag and nail E'ly side	227° 10'	151.32'
NW corner barn (concrete block)	144° 43'	123.05'
USC & GS station Kotman	89° 12' 49"	2055.07'



Signed by Steven Lampen Date December 12, 1996
Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1978
REVISED JAN. 1983
ADAPTED FOR WORD PROCESSING MARCH, 1987