

**1999 Alpena County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

JAN 21 2000

For corners in

Alpena
(County)

Located In:

Corner Code #

SECTION

1. Public Land Survey

T 29N R5E
T _____ R _____
T _____ R _____
T _____ R _____

K-1

2. Property Controlling in Section

S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____
S _____ T _____ R _____

L- 2 P- 273
12/10/1999 01:39P
Page: 1 of 1
Kathy J. Matash, Register Alpena Co., MI LDC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel T. Kibbe, in a field survey on June 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: GLO Survey by Lewis Clason: Intersected North Boundry 12 links East of post. Referenced: Hemlock 16-S48E-28/Beech 6-S64W-23.
- 1958: Plat of Behnke's Sub James L. Scott: Referenced corner.
- 1958: Plat of Behnke's addition James L. Scott: Referenced corner.
- 1958: Plat of Beaver Shores James L. Scott: Referenced corner.
- 1971: Survey by James L. Scott: Referenced corner.
- Survey Witnesses by Gary St. Charles: 3/4" pipe. Referenced: P. Pole-N79W-70.40'/P. Pole-S10E-78.32'/Anchor Pole-S40W-84.49'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1999: Remon. Survey by Daniel T. Kibbe. Found 3/4" pipe in Monument Box, 33' North of CL Beaver Lake Road, 15' East of CL O'Hum. This monument box is determined to be K-13 T30N R5E. Contractor found no evidence of K-1 position. Contractor proposes to set corner at GLO position 12 links (7.92 feet) East of K-13 T30N R5E.

This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1999: Placed 3" Alpena County cap stamped to identify the corner over 1/2" iron rod. Referenced:
P. Pole-set tag- S18E 74.48'
Anchor Pole-set tag- S48W 89.37'
P. Pole-set tag- N82W 78.44'
K-13 Remon. cap in monument box west 7.92'

P.A. 345 ALPENA COUNTY
PEER APPROVED 9/16/99
D.P.B. t

Signed by Daniel T. Kibbe
Surveyor's Michigan License No. 37278



Date November 30, 1999