

**1999 Alpena County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alpena
(County)

Located In:

Corner Code #

JAN 21 2000

SECTION

1. Public Land Survey T 29N R 5E
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

L-1



L-2 P-276

12/10/1999 01:39P

Page: 1 of 1

Kathy J. Matash, Register Alpena Co., MI LDC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel T. Kibbe, in a field survey on June 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

Not a GLO Corner

Survey Witness Sheet, Gary St. Charles. No corner found. No deflection on North Sec. Line according to Jim Scott (Scott Engineering) 66' R.O.W South of Section line.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1999: Remon. Survey by Daniel T. Kibbe-Contractor found no evidence of L-1 position. Contractor proposes to set corner at 6 links (3.96') East of L13 T30N R5E. This is a 1/2 the distance of the K1 T29N R5E / K13 T30N R5E position.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1999: Placed 3" Alpena County cap stamped to identify the corner over 1/2" iron rod.

Referenced:

- 26" Twin Oak-found Fabis tag-N02W 12.84'
- 26" Oak-found Fabis tag-N50W 15.31'
- 7" Tri Maple-found Fabis tag-N72W 15.18'
- Remon. corner L-13 West 3.96'


P.A. 345 ALPENA COUNTY

PEER APPROVED 9/16/99

D.T. Kibbe

Signed by *Daniel T. Kibbe*
Surveyor's Michigan License No. 37278

Date November 30, 1999



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983
REVISED OCT., 1995