

**1999 Alpena County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

JAN 21 2000

SECTION

For corners in

Alpena
(County)

Located In:

Corner Code #

1. Public Land Survey

T 29N R 5E

M-5 ✓

T 29N R 6E

A-5

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

L- 2 P- 270
12/10/1999 01:39P
Page: 1 of 1
Kathy J. Matash, Register Alpena Co., MI LDC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Daniel T. Kibbe, in a field survey on June 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: GLO Survey by Lewis Clason. Set post. Referenced: Y. Pine 16-S23W-56/Y. Pine 17-N39W-46
- 1908: County Survey by Jos. W. McNeil. Found corner plain, one OBT down and partly burned. Set large cedar stake and NWT. Referenced: Y. Pine stump 16-S23W-56 (OBT)/Y. Pine 17-N39W-46 (OBT) B. Oak 12-S67W-92 (NWT)
- 1959: MDOT Survey by N.C. Caldwell. Dug 6'x6'x3' and could not locate old corner. Set 1" bar by single proportion. 2.87' Rt. Sta. 333+19.29. Fence in line West. Referenced: 16" Oak-S72W-77.20/12" N. Pine-S45W-89.68/10" Oak-S80E-90.17'
- 1959: MDOT Recorded Corner by N.C. Caldwell. Dug 6'x6'x3' and could not locate old corner. Set 1" bar by single proportion. 2.87' Rt. Sta. 333+19.29./Fence in line West. Referenced: 16" Oak-S72W-77.20/12"N. Pine-S45W-89.68/10" Oak-S80E-90.17'
- 1959: MDOT Survey by N.C. Caldwell. Found 3/4" pipe. Referenced: "x" in Guardrail post-N40E-26.21/"x" Guardrail post-N35W-36.00'/P. Pole-E-S27E-153.46'
- 1962: MDOT Recorded corner by Gerald Wozniack. 1 1/4" Pipe in mon. box 2.87' Rt. of C/L M-65. Referenced: "x" Guardrail post-N40E-26.21/"x" Guardrail post-N35W-36.00'/P.Pole-S27E-153.46'.
- 1962: Witness records by Porter survey. 1 1/4" Pipe in mon. box 2.87' Rt. of C/L M-65. (Gerald Wozniack MSHD) Referenced: "x" Guardrail post-N40E-26.21/"x" Guardrail post-N35W-36.00'/P.Pole-S27E-153.46'.
- 1985: Survey by Earl T. Lewis. Existing mon. box. Referenced: Power pole-S50E-149.3'/ROW Marker-East-75'.
- 1994: MDOT Recorded Corner by Clifford C. Lindgren. Found 1 1/4" pipe in mon. box after construction 3.6' East of M-65 C/L 2.87' East of C/L before construction. Referenced: N/Tag top of WD Block Guard Rail-S55W-36.64/N/Tag top of WD Block Guard Rail-N25W-50.73/N/Tag P. Pole-S20E-149.02'/N/Tag P.Pole-N28E-212.66'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1999: Remon. Survey by Daniel T. Kibbe. Found 1 1/4" pipe in mon. box 3' East of M-65 CL.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1999: Placed 3" Alpena County cap stamped to identify the corner over 1/2" iron rod in 1 1/4" pipe in monument box.
Referenced:

- Top of Wood Block Guard Rail-set tag-S30E 33.00'
- Top of Wood Block Guard Rail-found MDOT tag-S51W 36.66'
- Top of Wood Block Guard Rail-found MDOT tag-N29W 50.73'
- Top of Wood Block Guard Rail-set tag-N32E 39.98'

P.A. 345 ALPENA COUNTY
PEER APPROVED 9/16/99
D. D. H. [Signature]

Signed by Daniel T. Kibbe

Date November 30, 1999

Surveyor's Michigan License No. 37278

